

QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	FULL C.E.	EROSION CONTROL	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
									10348		10348		SY	TEMPORARY EROSION MATTING	653.20				
									6		6		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
									150		150		CY	VEHICLE TRACKING PAD	653.35				
									24		24		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
									5		5		EACH	FILTER BAG	653.45				
									1470		1470		LF	BARRIER FENCE	653.50				
									6700		6700		LF	PROJECT DEMARCATION FENCE	653.55				
						145					145		SF	TRAFFIC SIGNS, TYPE A	675.20				
						315					315		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						39					39		EACH	REMOVING SIGNS	675.50				
						12					12		EACH	ERECTING SALVAGED SIGNS	675.60				
						1					1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION (US ROUTE 2 / VT 14 S)	678.15				
						125					125		LF	ELECTRICAL CONDUIT (2")(PVC)(SCH 80)	678.21				
						360					360		LF	WIRED CONDUIT (2")(PVC)(SCH 80)	678.23				
						120					120		LF	ELECTRICAL WIRING	678.24				
						1					1		EACH	STREET LIGHT ASSEMBLY	679.46				
						1					1		EACH	BRACKET ARM	679.47				
						1					1		EACH	LUMINAIRE	679.50				
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
						208000					208000		DL	SPECIAL PROVISION (UNIFORMED TRAFFIC OFFICERS)(N.A.B.I.)	900.615				
						15					15		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
									57		57		EACH	SPECIAL PROVISION (INLET PROTECTION DEVICE, FILTER FIBER)	900.620				
						2					2		EACH	SPECIAL PROVISION (JUNCTION BOX, HEAVY DUTY)	900.620				
						4					4		EACH	SPECIAL PROVISION (SOIL BEARING SLIP BASE)(2 1/2")	900.620				
						75					75		LF	SPECIAL PROVISION (24" GRANITE BACK CURB)	900.640				
										371	371		LF	SPECIAL PROVISION (BRIDGE RAILING, TEXAS)	900.640				
										290	290		LF	SPECIAL PROVISION (DRILLED SHAFT IN EARTH)(6 FT)	900.640				
										20	20		LF	SPECIAL PROVISION (DRILLED SHAFT OBSTRUCTION DRILLING AND REMOVAL)	900.640				
										103	103		LF	SPECIAL PROVISION (GUARDRAIL APPR. SECTION TO CONC. BR. RAILING)(TL-2)	900.640				
						120					120		LF	SPECIAL PROVISION (PEDESTRIAN RAILING, STEEL)	900.640				
						1					1		LS	SPECIAL PROVISION (INFILTRATION TRENCH AND SAND FILTER)	900.645				
										1	1		LS	SPECIAL PROVISION (MOBILIZATION OF DRILLED SHAFT EQUIPMENT)	900.645				
						1					1		LS	SPECIAL PROVISION (PRECAST CONCRETE GRAVITY RETAINING WALL)	900.645				
										1	1		LS	SPECIAL PROVISION (TEMPORARY STEEL SHEET PILING)	900.645				
						1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
										8125	8125		SF	SPECIAL PROVISION (PRECAST CONCRETE DECK PANEL)(8 1/2 IN.)	900.670				
						155					155		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675				
						60				5	65		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683				

PROJECT NAME: EAST MONTPELIER
 PROJECT NUMBER: BRF 037-I(7)
 FILE NAME: 06_Quantities.dgn
 PROJECT LEADER: T. KNIGHT
 DESIGNED BY: K. RICHARDSON
 QUANTITY SHEET 05 4
 PLOT DATE: 2/17/2017
 DRAWN BY: C. GENDRON
 CHECKED BY: D. YOULEN
 SHEET 9 OF 158

