ROUTE	STATION	OFFSET	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
EAST MONTPELIER																													
			M1-4	24	24	BLK WHT		4.00																			X		
			M6-1	21	15	BLK WHT		2.19																			X		
			M3-1	24	12	GRN WHT		2.00																			X		
			M1-5	24	24	GRN WHT		4.00																					E-136B
			M6-1	21	15	GRN WHT		2.19																			X		
VT 14	129+55	LT	VD-701	6	10		BRIDGE 68 VT 14	0.42								1	X												T-42
U.S. ROUTE 2																													
U.S. 2	142+78	LT	VD2-1	72	12		MONTPELIER 7				1				X														
			M3-4	24	12		WEST				1																		
			M1-4	24	24		U.S. ROUTE 2				1																		
			VD-503	12	18		CROSS VT TRAIL				1																		
			VD2-1	72	12		MONTPELIER 7					1				2		X											
			M3-4	24	12		WEST					1																	
			M1-4	24	24		U.S. ROUTE 2					1																	
			VD-503	12	18		CROSS VT TRAIL					1																	
							SHEET TOTALS	14.80	0.00	0	4	4	0	0	0	3	45			0	0	0	0	0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN TOTALS	146.59	0.00	0.0	12.0	12.0	0.0	0.0	0.0	22	330.0			0	0.0	0.0	0.0	0.0					

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: EAST MONTPELIER
PROJECT NUMBER: BRF 037-1(7)
FILE NAME: EAST MONTPELIER TSS
PROJECT MANAGER T. KNIGHT
DESIGNED BY: G. BARRETT
PLOT DATE: 2/8/2017
DRAWN BY: G. BARRETT
CHECKED BY: D. DRAPER