ROUTE	STATION	OFFSET	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
EAST MONTPELIER																													
			M6-1	21	15		LEFT ARROW					1																	
			M3-4	24	12		WEST					1																	
			M1-4	24	24		U.S ROUTE 2					1																	
			M6-2	21	15		DIAGONAL ARROW (45 DEGREES UP, RIGHT)					1																	
U.S. 2	150+63	LT	W3-3	30	30			6.25								1		X									X		
U.S. 2			R10-7	24	30			5.00								1		X								INSTALL SIGN OFF PROJECT ON U.S. ROUTE 2. SEE SHEET TSL 3 FOR LOCATION			
							SHEET TOTALS	11.25 SF	0.00 SF	0 EA	0 EA	4 EA	0 EA	0 EA	0 EA	2 EA		30 FT		0 EA	0 LB	0 LB	0 LB	0 LB				
							TOWN TOTALS	146.59	0.00	0.0	12.0	12.0	0.0	0.0	0.0	22		330.0		0	0.0	0.0	0.0	0.0				

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **EAST MONTPELIER**
PROJECT NUMBER: **BRF 037-1(7)**

FILE NAME: **EAST MONTPELIER TSS** PLOT DATE: **2/8/2017**
PROJECT MANAGER **T. KNIGHT** DRAWN BY: **G. BARRETT**
DESIGNED BY: **G. BARRETT** CHECKED BY: **D. DRAPER**