



TRAFFIC DATA

| YEAR | ADT | DHV | % D | % T | ADTT |
|------|------|-----|-----|-----|------|
| 2017 | 5700 | 640 | 62 | 5.8 | 320 |
| 2037 | 6300 | 710 | 62 | 9.4 | 590 |

18 kip ESAL for flexible pavement from 2017 to 2037: 2,920,000
18 kip ESAL for flexible pavement from 2017 to 2057: 7,186,000
Design speed: 25 MPH
Posted speed: 35 mph, warned for 25 mph within project limits

VT RTE 14 - SOUTH TO BARRE

TRAFFIC DATA

| YEAR | ADT | DHV | % D | % T | ADTT |
|------|--------|------|-----|-----|------|
| 2017 | 10,600 | 1200 | 78 | 5.2 | 600 |
| 2037 | 11,900 | 1300 | 78 | 7.8 | 1000 |

18 kip ESAL for flexible pavement from 2017 to 2037: 5,785,000
18 kip ESAL for flexible pavement from 2017 to 2057: 13,791,000
Design speed: 25 MPH
Posted speed: 35 mph, warned for 25 mph within project limits

US 2 - WEST TO MONTPELIER

TRAFFIC DATA

| YEAR | ADT | DHV | % D | % T | ADTT |
|------|--------|------|-----|-----|------|
| 2017 | 13,200 | 1500 | 77 | 4.9 | 730 |
| 2037 | 14,800 | 1700 | 77 | 7.3 | 1200 |

18 kip ESAL for flexible pavement from 2017 to 2037: 7,067,000
18 kip ESAL for flexible pavement from 2017 to 2057: 16,823,000
Design speed: 25 MPH
Posted speed: 35 mph, warned for 25 mph within project limits

US 2 - EAST TO PLAINFIELD

PROJECT NAME: EAST MONTPELIER
PROJECT NUMBER: BRF 037-(117)

FILE NAME: 26a2a_Traffic Data.dgn PLOT DATE: 2/17/2017
PROJECT LEADER: T. KNIGHT DRAWN BY: S. NEELY
DESIGNED BY: D. DEBAIE CHECKED BY: K. RICHARDSON
VT 14 & US 2 TRAFFIC DATA TRD 1 SHEET 59 OF 158

