

# QUANTITY SHEET #2

SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
PIERS	ABUTMENT #1	ABUTMENT #2	SUPERSTR UCTURE	APPROACH SLAB#1	APPROACH SLAB#2	FULL C.E ITEMS	TRAINING	EROSION CONTROL	ROADWAY QUANTITY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS			
									84			84		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B (MOD.)	616.28						
									3			3		EA	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12						
									18			18		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH (MOD.)	618.10						
									254			254		LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20						
									2			2		EA	ENERGY ABSORPTION ATTENUATOR (SAND - FILLED PLASTIC BARREL)	621.56						
									1			1		EA	ANCHOR FOR STEEL BEAM RAIL	621.60						
									120			120		LF	ALUMNUM APPROACH RAILING (MOD. - ANODIZED BLACK)	621.74						
									373			373		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80						
									1100			1100		LF	TEMPORARY TRAFFIC BARRIER	621.90						
									50			50		HR	UNIFORMED TRAFFIC OFFICERS	630.10						
									500			500		HR	FLAGGERS	630.15						
						1						1		LS	FIELD OFFICE - ENGINEERS	631.10						
						1						1		LS	TESTING EQUIPMENT - CONCRETE	631.16						
						1						1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17						
						1						1		LS	TESTING EQUIPMENT - PROTECTIVE COATINGS	631.18						
						1						1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			(N.A.B.I.) = NOT A BID ITEM			
							520					520		HR	EMPLOYEE TRAINEESHIP	634.10						
									1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11						
									1			1		LS	TRAFFIC CONTROL	641.10						
									1600			1600		LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40						
									1410			1410		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41						
									330			330		LF	DURABLE 8" WHITE LINE (THERMOPLASTIC)	646.42						
									18			18		LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46						
									4			4		EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50						
									3000			3000		LF	TEMPORARY 4" WHITE LINE (TAPE, TYPE I)	646.60						
									100			100		LF	TEMPORARY 4" YELLOW LINE (TAPE, TYPE I)	646.61						
									40			40		LF	TEMPORARY 24" STOP BAR (PAINT)	646.66						
									100			100		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85						
								10				10		SY	GEOTEXTILE UNDER STONE FILL	649.31						
								160				160		SY	GEOTEXTILE FOR SILT FENCE	649.51						
								10				10		LB	SEED	651.15						
								10				10		LB	SEED - WINTER RYE	651.17						
								30				30		LB	FERTILIZER	651.18						
								1				1		TON	AGRICULTURAL LIMESTONE	651.20						
								1				1		TON	HAY MULCH	651.25						
								10				10		EA	HAY BALES FOR EROSION CONTROL	651.26						
								40				40		CY	TOPSOIL	651.35						
								10				10		SY	EROSION MATTING	654.10						

PROJECT NAME: **CAMBRIDGE**  
PROJECT NUMBER: **BHF 030-2 (19) 5**  
FILE NAME: form99.dgn PLOT DATE: 11/7/2006  
PROJECT LEADER: R. R. WHITCOMB DRAWN BY: C. CARLSON  
DESIGNED BY: B. W. ENST CHECKED BY: G. ROY  
QUANTITY SHEET #2 SHEET 5 OF 68