STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

ST. ALBANS - SWANTON STP 2335(I)S			ST. ALBANS - HIGHGATE STP 2114(I)S							
EMPLOYEE TRAINEE-SHIP	BRIDGE	ROADWAY	EMPLOYEE TRAINEE-SHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
		2				2	EA	DURABLE RAILROAD CROSSING SYMBOL (MOD. I)	646.52	
		43740			44500	88240	M	TEMPORARY 100 mm WHITE LINE	646.60	
		39300			39000	78300	M	TEMPORARY 100 mm YELLOW LINE	646.61	
					3030	3030	M	TEMPORARY 150 mm WHITE LINE	646.614	
					2300	2300	M	TEMPORARY 150 mm YELLOW LINE	646.615	
		415			330	745	M	TEMPORARY 200 mm YELLOW LINE	646.63	
		23			740	763	M	TEMPORARY 300 mm WHITE LINE	646.64	
		206			170	376	M	TEMPORARY 600 mm STOP BAR	646.66	
		152			162	314	EA	TEMPORARY LETTERS OR SYMBOLS	646.70	
		4				4	EA	TEMPORARY RAILROAD CROSSING SYMBOL	646.72	
		900			990	1890	EA	LINE STRIPING TARGETS	646.76	
					170	170	M	PAINTED CURB	646.81	
		155			200	355	m²	GEOTEXTILE UNDER STONE FILL	649.31	
		20			20	40	KG	SEED	651.15	
		120			120	240	KG	FERTILIZER	651.18	
		1			1	2	T	AGRICULTURAL LIMESTONE	651.20	
		1			1	2	T	HAY MULCH	651.25	
		20			20	40	m³	TOPSOIL	651.35	
		2225			4500	6725	m³	EROSION MATTING	654.10	
		10			25	35	m²	TRAFFIC SIGNS, TYPE A	675.20	
								BEGIN OPTION ITEMS		
		130			180	310	M	FLANGED CHANNEL SIGN POST	675.301	
		130			180	310	M	SQUARE TUBE SIGN POSTS WITH ANCHOR	675.341	
								END OPTION ITEMS		
		49			57	106	EA	REMOVING SIGNS	675.50	
		27			19	46	EA	ERECTING SALVAGED SIGNS	675.60	
		6			22	28	EA	DELINEATORS W/ STEEL POSTS	676.10	
		463			100	563	M	VEHICLE LOOP DETECTOR	678.22	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME AND NUMBER :
ST. ALBANS - HIGHGATE STP 2114(I)S
ST. ALBANS - SWANTON STP 2335(I)S

DESIGN FILE NAME: /pave/98c110/pc10.dgn
IPARM FILE NAME: pc166cqs3.i
SURVEYED BY: D-H
SQUAD LEADER:
PLOT DATE: 16-SEP-2005 13
SURVEY DATE: 07/22/99
DRAWN BY: D-H
SHEET: 5 OF 89