STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
ST. ALBANS 0+060.0, RT.		1	900	900	0.81						2			X		X																		E-155M	
0+070.0, RT.		1	900	900	0.81						2			X		X																		E-155M	
0+128.2, LT.		1	900	750	0.68						1			X		X																		E-145AM	
0+223.0, LT.		1	900	900	0.81						2			X		X																		E-152M	
0+284.5, RT.		1	900	600	0.54																											MOUNT BACK TO BACK WITH EXISTING D-BOARDS ON EXISTING POST.		E-143M
0+340.0, RT.		1	750	750	0.56																											MOUNT BACK TO BACK WITH EXISTING ROUTE SIGNS ON EXISTING POST.		E-143M
0+344.5, LT.		1	750	750	0.56																											MOUNT STOP SIGN BACK TO BACK WITH EXISTING SIGNS ON EXISTING POST.		E-143M
0+360.8, LT.		1	750	750	0.56																											MOUNT STOP SIGN BACK TO BACK WITH EXISTING SIGNS ON EXISTING POST.		E-143M
0+423.0, RT.		1	900	600	0.54																											MOUNT BACK TO BACK WITH EXISTING D-BOARDS ON EXISTING POST.		E-143M
0+479.0, RT.		1	750	750	0.56																											MOUNT BACK TO BACK WITH EXISTING ROUTE SIGNS ON EXISTING POST.		E-143M
0+484.5, RT.		1	750	750	0.56																											MOUNT STOP SIGN BACK TO BACK WITH EXISTING SIGNS ON EXISTING POST.		E-143M
0+504.2, RT.		1	750	750	0.56																											MOUNT STOP SIGN BACK TO BACK WITH EXISTING SIGNS ON EXISTING POST.		E-143M
												m	m	m 18.4	m	m 18.4	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² 7.55	m²	EA.	m²				m 18.4			m 18.4						kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
ST. ALBANS - HIGHGATE	STP 2114(1)S

DESIGN FILE NAME: /pave/98c110/pc110.dgn
IPARM FILE NAME: pc110tsl.1
SURVEYED BY: D-H
SQUAD LEADER:
PLOT DATE: 16-SEP-2005 13
SURVEY DATE: 07/22/99
DRAWN BY: D-H
SHEET: 41 OF 89