STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
SWANTON (CONT.)														OPTION ITEMS																					
1+303.0, RT.	SUGAR MAPLE DR STOP 0070 0615 0080 B-B						1																										INSTALL SALVAGED STREET SIGN 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET; INSTALL NEW STOP SIGN AND SALVAGED REFERENCE PLAQUE BACK TO BACK ON NEW POST.	-	-
		1	750	750	0.56						1			X			X																	E-143M
1+339.8, LT.	MOUNTAIN VIEW DR STOP 0070 0615 0083 B-B						1																										INSTALL SALVAGED STREET SIGN 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET; INSTALL NEW STOP SIGN AND SALVAGED REFERENCE PLAQUE BACK TO BACK ON NEW POST.	-	-
		1	750	750	0.56						1			X			X																	E-143M
1+349.6, LT.	LEGAL LOAD LIMIT 24,000 POUNDS						1				1			X			X																	-	-
1+495.3, LT.	CONSTOCK RD STOP						1																										INSTALL SALVAGED STREET SIGN 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET, MOUNTED ON NEW POST.	-	-
		1	750	750	0.56						1			X			X																	E-143M
1+508.5, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
2+468.5, LT.	LIME KILN RD STOP 0070 0615 0153 B-B						1																										INSTALL SALVAGED STREET SIGN 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET; INSTALL NEW STOP SIGN AND SALVAGED REFERENCE PLAQUE BACK TO BACK ON NEW POST.	-	-
		1	750	750	0.56						1			X			X																	E-143M
2+479.5, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
2+668.6, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X			X																		E-141M
2+678.6, RT.	BACHAND RD STOP						1																										INSTALL SALVAGED STREET SIGN 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET, MOUNTED ON NEW POST.	-	-
		1	750	750	0.56						1			X			X																	E-143M
TOTALS		m² 4.15		m²	EA. 9	m²						m 41.4			m 41.4				EA	kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ST. ALBANS - SWANTON
PROJECT NUMBER: STP 2335(I)S

FILE NAME: /pave/01c016/p01c016.dgn
PROJECT LEADER: JLL
DESIGNED BY: D-H
IPARM FILE NAME: p01c016tss2.i
PLOT DATE: 16-SEP-2005
DRAWN BY: D-H
CHECKED BY: D-H
SHEET 87 OF 89