STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						150	150	EA	YIELDING MARKER POSTS	619.17	EST.
						3790	3790	m	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	9
						1400	1400	m	STEEL BEAM GUARDRAIL (MOD.-2.4 m POSTS) (GALVANIZED)	621.20	3
						8	8	m	HEAVY DUTY STEEL BEAM GUARDRAIL (GALVANIZED)	621.21	0
						89	89	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	0
						5	5	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	EST.
						38	38	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	0
						270	270	m	REMOVING AND RESET GUARDRAIL	621.75	0
						100	100	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST.
						150	150	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	EST.
						2910	2910	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	6
						20	20	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	0
						1620	1620	HR	UNIFORMED TRAFFIC OFFICERS	630.10	22
						2500	2500	HR	FLAGGERS	630.15	105
						1	1	LS	FIELD OFFICE ENGINEERS	631.10	-
						1	1	LS	TESTING EQUIPMENT-BITUMINOUS	631.17	-
						1	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
				520			520	HR	EMPLOYEE TRAINEESHIP	634.10	0
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						53 830	53 830	m	DURABLE 100 mm WHITE LINE (THERMOPLASTIC)	646.40	540
						46 050	46 050	m	DURABLE 100 mm YELLOW LINE (THERMOPLASTIC)	646.41	459
						100	100	m	DURABLE 150 mm WHITE LINE (THERMOPLASTIC)	646.414	7
						100	100	m	DURABLE 150 mm YELLOW LINE (THERMOPLASTIC)	646.415	3
						155	155	m	DURABLE 600 mm STOP BAR (THERMOPLASTIC)	646.46	1
						102	102	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	0
						35	35	m	DURABLE CROSSWALK MARKINGS W/ DIAGONAL LINES (THERMOPLASTIC)	646.51	1
						53 830	53 830	m	TEMPORARY 100 mm WHITE LINE	646.60	540
						46 050	46 050	m	TEMPORARY 100 mm YELLOW LINE	646.61	459

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT : HARTFORD - ROYALTON

PROJECT NO. : STP 2121(1)S

DESIGN FILE NAME: /pave/98cl74/pcl74.dgn
IPARM FILE NAME: pcl74qs02.i
PLOT DATE: 21-MAR-2007 09
SURVEYED BY: CLD ENGINEERS INC
SURVEY DATE: 8/99
SQUAD LEADER: WRH
DRAWN BY: MPS
SHEET: 6 OF 64