STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
															OPTION ITEMS																						
HARTFORD																																			
STA 2+893 RT	DOTHAN RD						1				1			4.1m X	09/19/06		X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1408 0180	1 1	750 150	750 200	0.56 0.03																											BACK TO BACK		E-143M E-138M
STA 5+182 RT	LEGAL LOAD LIMIT 16,000 POUNDS	1	600	750	0.45						1			4.1m X	09/19/06		X																		E-141M
STA 5+192 RT	BYRON HILL RD						1				1			4.0m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1408 0323	1 1	750 150	750 200	0.56 0.03									09/19/06																			BACK TO BACK		E-143M E-138M
STA 6+181 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45		09/19/06				1			4.0m X			X																		E-141M
STA ~~6+191~~ 181 RT	RUNNALS RD				09/19/06		1				1			3.7m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
6+191 RT	STOP 0140 1408 0384	1 1	750 150	750 200	0.56 0.03	09/19/06								4.0m X																			BACK TO BACK		E-138M
			09/18/06																															
STA 7+776 RT	LEGAL LOAD LIMIT 16,000 POUNDS	1	600	750	0.45						1			3.7m X			X																		E-141M
STA 7+793 RT	JERICHO ST		09/18/06				1				1			4.1m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1408 0482	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
												m	m	m 32.2	m	m	m 32.2		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS		m² 3.26	m²	EA. 4	m²							m 32.2			m 32.2					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : HARTFORD - ROYALTON	PROJECT NO. : STP 2121(I)S
DESIGN FILE NAME: /pave/98cl74/pcl74.dgn	
IPARM FILE NAME: pcl74ts01.i	PLOT DATE: 21-MAR-2007_0
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 8/99
SQUAD LEADER: WRH	DRAWN BY: REB
	SHEET: 57 OF 64