STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
STA 8+031 RT	LEGAL LOAD LIMIT 16,000 POUNDS	1	600	750	0.45	09/18/06					1			4.1m X			X																			E-141M
STA 8+064 RT	JERICHO ST						1				1			4.1m X			X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1408 0502	1 1	750 150	750 200	0.56 0.03	09/18/06																											BACK TO BACK		E-143M E-138M
STA 10+840 RT	~~POMFRET~~	1	1800	250	0.45						~~2~~			~~X~~			X																	ELIMINATE SIGN		E-123M
	~~QUECHEE~~	1	1800	250	0.45																														E-123M
STA 11+077 LT	~~STOP~~ 0140 1408 0690	1 1	750 150	750 200	~~0.56~~ 0.03				1		~~1~~			~~X~~			X																	NO SIGN W/ BRIDGE PROJECT BACK TO BACK		E-143M E-138M
STA 11+229 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	09/18/06 750	0.45						1			4.1m X			X																			E-141M
STA 11+235 RT	HARPER SAVAGE LN		09/18/06				1				1			4.1m X			X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1408 0697	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
STA 11+357 LT	~~POMFRET~~ →	1	1800	250	0.45						2			X			X																	ELIMINATE SIGN		E-123M
	~~QUECHEE~~ →	1	1800	250	0.45																														E-123M
STA 11+687 RT	TIGERTOWN RD		09/18/06				1				1			4.1m X			X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1408 0725	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
											m	m	m 40.6		m	m	m 40.6	EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m² 5.06	m²	EA. 3	m²						m 40.6				m 40.6				kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
HARTFORD - ROYALTON	STP 2121(I)S

DESIGN FILE NAME: __/pave/98cl74/pcl74.dgn
IPARM FILE NAME: pcl74ts02.i PLOT DATE: 21-MAR-2007_0
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 8/99
SQUAD LEADER: WRH DRAWN BY: REB
SHEET: 58 OF 64