STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
SHARON																																			
STA 0+013 RT	LEGAL LOAD LIMIT 24,000 POUNDS 09/18/06	1	600	750	0.45						1			5.2m X			X																	E-141M
	SPEED LIMIT 25	1	600	750	0.45																													E-142M
STA 0+023 RT	TH 43 SHARHART RD 09/18/06						1				1			4.1m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1417 0001	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
STA 6+064 RT	TH 11 QUIMBY MOUNTAIN RD 09/18/06						1				1			4.1m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1417 0376	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
STA 8+564 RT	LEGAL LOAD LIMIT 24,000 POUNDS 09/18/06	1	600	750	0.45						1			4.3m X			X																	E-141M
STA 8+574 RT	TH 17 FAY BROOK RD 09/18/06						1				1			4.0m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0140 1417 0533	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
STA 8+608 LT	TH 3 RIVER RD 09/18/06						1				1			4.3m X			X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 09/18/06 0140 1417 0535	1 1	750 150	750 200	0.56 0.03																												BACK TO BACK		E-143M E-138M
10+900 RT	STOP 09/18/06	1	750	750	0.56				1																										
												m	m	27.6	m	m	27.6		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS		m² 3.71	m²	EA. 4	m²							m 27.6			m 27.6					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : HARTFORD - ROYALTON	PROJECT NO. : STP 2121(I)S
DESIGN FILE NAME: /pave/98cl74/pcl74.dgn	
IPARM FILE NAME: pcl74ts03.i	PLOT DATE: 21-MAR-2007_0
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 8/99
SQUAD LEADER: WRH	DRAWN BY: REB
	SHEET: 59 OF 64