STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	EMPLOYEE TRAINEESHIP	FULL CE	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				280	280	LF	H.D. STEEL BEAM GUARD RAIL, GALVANIZED	621.21	2.4
				31	31	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	--
				14	14	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARD RAIL	621.53	--
				13	13	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	--
				9,500	9,500	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	12.4
				1,500	1,500	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				5,000	5,000	HR	FLAGGERS	630.15	EST
		1			1	LS	FIELD OFFICE, ENGINEERS	631.10	--
		1			1	LS	TESTING EQUIPMENT, CONCRETE	631.16	--
		1			1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	--
		1			1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	EST
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				72,000	72,000	LF	DURABLE 4 IN WHITE LINE, THERMOPLASTIC	646.402	--
				72,000	72,000	LF	DURABLE 4 IN YELLOW LINE, THERMOPLASTIC	646.412	--
				240	240	LF	DURABLE 8 IN WHITE LINE, THERMOPLASTIC	646.442	--
				300	300	LF	DURABLE 24 IN STOP BAR, THERMOPLASTIC	646.482	--
				77	77	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	--
				112,500	112,500	LF	TEMPORARY 4 IN WHITE LINE, PAINT	646.602	EST
				112,500	112,500	LF	TEMPORARY 4 IN YELLOW LINE, PAINT	646.612	EST
				600	600	LF	TEMPORARY 24 IN STOP BAR, PAINT	646.682	EST
				154	154	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	--
				2,000	2,000	EA	LINE STRIPING TARGETS	646.76	EST
				2,250	2,250	SY	GEOTEXTILE UNDER STONE FILL	649.31	13
				120	120	LB	SEED	651.15	EST
				1,000	1,000	LB	FERTILIZER	651.18	EST
				4	4	TON	AGRICULTURAL LIMESTONE	651.20	EST
				4	4	TON	HAY MULCH	651.25	EST
				100	100	CY	TOPSOIL	651.35	EST
				575	575	SY	TEMPORARY EROSION MATTING	653.20	14
				143	143	SF	TRAFFIC SIGNS, TYPE A	675.20	0.88
							- BEGIN OPTION ITEMS -		
				345	345	LF	FLANGED CHANNEL SIGN POSTS	675.301	EST
				345	345	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST
							- END OPTION ITEMS -		
				33	33	EA	REMOVING SIGNS	675.50	--
				5	5	EA	ERECTING SALVAGED SIGNS	675.60	--
				48	48	EA	DELINEATORS WITH STEEL POST	676.10	EST
				1	1	EA	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	EST
			115		115	LF	SPECIAL PROVISION (BRIDGE RAILING REPAIR, TYPE II)	900.640	2.5
				9,300	9,300	TON	SPECIAL PROVISION (SUBBASE, RAP)	900.680	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS

TOTALS

QUANTITY SHEET #2

PROJECT NAME **MONTGOMERY - BERKSHIRE** p98cl82.dgn
PROJECT NUMBER **STP 2125(1)S** p98cl82qs2.i

DATE PLOTTED 10-FEB-2010 14: