STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET # 1

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

		FULL E & C	NON GOVT PARTIC	BRIDGE		ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						325	325	CM	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	
						600	600	CM	EARTH BORROW	203.30	
						1	1	CM	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
						41,300	41,300	SM	COLD PLANING, BITUMINOUS PAVEMENT	210.10	53
						3,000	3,000	T	AGGREGATE SHOULDER, RAP	402.13	43
						34,360	34,360	KG	EMULSIFIED ASPHALT	404.65	-
						19,000	19,000	T	BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	406.25	353
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	406.28	-
						1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29	-
						1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	406.30	-
						1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	406.31	-
						1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
				14			14	M	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	
						60	60	M	375 CPEP	601.0910	EST
						25	25	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES CLASS I	604.412	-
						1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES CLASS III	604.418	EST.
			5				5	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
						210	210	HR	POWER GRADER RENTAL	608.15	EST
						220	220	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						75	75	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
						75	75	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
						220	220	HR	TRUCK RENTAL	608.37	EST
						210	210	HR	LOADER RENTAL, TYPE I	608.40	EST
						8975	8975	CM	DUST CONTROL WITH WATER	609.10	
						725	725	CM	STONE FILL, TYPE I	613.10	
						450	450	M	TREATED TIMBER CURB	616.35	53
						45	45	T	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	.36
						52	52	EA	YIELDING MARKER POSTS	619.17	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BITUMINOUS CONCRETE GUTTER AND ISLANDS
		TYPE II (PG 64-28)
40.54	T	VT. 142 TO BE USED AT SELECT CULVERT LOCATIONS
4.1	T	PAVED GUTTER
44.64	T	TOTAL
0.36	T	ROUNDING
45	T	GRAND TOTAL
		BITUMINOUS CONCRETE PAVEMENT TYPE III (PG 64-28)
13,813	T	VT. 142
146	T	DRIVES
144	T	SIDEROADS
400	T	PULLOUTS
14,503	T	TOTAL TYPE III
		BITUMINOUS CONCRETE PAVEMENT TYPE IV (PG 64-28)
4,144	T	VT. 142
14,503	T	TYPE III
4,144	T	TYPE IV
18,647	T	TOTAL
353	T	ROUNDING
19,000	T	GRAND TOTAL
		AGGREGATE SHOULDER, RAP
2,005	T	SHOULDERS
150	T	GUARDRAIL BUBBLES
802	T	BACKING UP OF NEW PAVEMENT
2,957	T	TOTAL
43	T	ROUNDING
3,000	T	GRAND TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: VERNON - BRATTLEBORO
PROJECT NUMBER: AC STP 2126(1)S

FILE NAME: /pave/98c184/pc184.dgn
PROJECT LEADER:
IPARM NAME : pc184qs1.i

PLOT DATE: 08-SEP-2009 13:3
DRAWN BY: WILDER
CHECKED BY: PAVT MGMT
SHEET 5 OF 33