STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET # 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

		FULL E & C	NON GOVT. PARTIC.	BRIDGE	TRAINING	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						1785	1785	M	STEEL BEAM GUARD RAIL, GALVANIZED	621.20	0.8
						1680	1680	M	STEEL BEAM GUARD RAIL, GALVANIZED W/ 2.4 M POSTS	621.205	
						20	20	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
						26	26	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
						3105	3105	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	2
			7				7	EA	ADJUST ELEVATION OF VALVE BOXES	629.20	
						900	900	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						1350	1350	HR	FLAGGERS	630.15	EST.
		1					1	LS	FIELD OFFICE , ENGINEERS	631.10	-
		1					1	LS	TESTING EQUIPMENT , CONCRETE	631.16	-
		1					1	LS	TESTING EQUIPMENT , BITUMINOUS	631.17	-
		1					1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
					520		520	HR	EMPLOYEE TRAINEESHIP	634.10	-
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						31,900	31,900	M	DURABLE 100 MM WHITE LINE, THERMOPLASTIC	646.402	98
						30,400	30,400	M	DURABLE 100 MM YELLOW LINE, THERMOPLASTIC	646.412	91
						110	110	M	DURABLE 600 MM STOP BAR, THERMOPLASTIC	646.482	6
						68	68	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
						3	3	EA	DURABLE RAILROAD CROSSING SYMBOL, THERMOPLASTIC	646.512	-
						42,800	42,800	M	TEMPORARY 100 MM WHITE LINE, PAINT	646.602	24
						60,800	60,800	M	TEMPORARY 100 MM YELLOW LINE, PAINT	646.612	182
						220	220	M	TEMPORARY 600 MM WHITE LINE, PAINT	646.682	-
						68	68	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	
						3	3	EA	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712	
						1500	1500	EA	LINE STRIPING TARGETS	646.76	
						2350	2350	SM	GEOTEXTILE UNDER STONE FILL	649.31	
						15	15	KG	SEED	651.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: VERNON - BRATTLEBORO
PROJECT NUMBER: AC STP 2126(1)S

FILE NAME: /pave/98c184/pc184.dgn
PROJECT LEADER:
IPARM NAME : pc184qs2.i

PLOT DATE: 08-SEP-2009 13:3
DRAWN BY: WILDER
CHECKED BY: PAVT MGMT
SHEET 6 OF 33