

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					100					100		LF	ALUMINUM APPROACH RAILING, ANODIZED	621.745				
					180					180		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
					1050					1050		LF	TEMPORARY TRAFFIC BARRIER	621.90				
					1050					1050		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
					160					160		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
					1000					1000		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
						520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
					1					1		LS	TRAFFIC CONTROL	641.10				
					1780					1780		LF	4 INCH WHITE LINE	646.20				
					1680					1680		LF	4 INCH YELLOW LINE	646.21				
					21					21		LF	24 INCH STOP BAR	646.26				
					13					13		EACH	LETTER OR SYMBOL	646.30				
					670					670		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602				
					525					525		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612				
					50					50		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682				
					5					5		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692				
					865					865		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
							10			10		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							210			210		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							10			10		LB	SEED	651.15				
							10			10		LB	SEED, WINTER RYE	651.17				
							50			50		LB	FERTILIZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							1			1		TON	HAYMULCH	651.25				
							10			10		CY	TOPSOIL	651.35				
					2					2		EACH	DELINEATOR WITH STEEL POST	676.10				
					2			5		7		EACH	JUNCTION BOX	678.26				
								340		340		LF	ELECTRICAL CONDUIT SLEEVE (2")PVC)	678.30				
					1					1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
					4					4		EACH	TEMPORARY DETECTOR	678.42				
					1			475		476		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)	900.608				
								28		28		EACH	SPECIAL PROVISION (REFURBISH EXISTING BEARING DEVICE ASSEMBLY)	900.620				
								48		48		LF	SPECIAL PROVISION (DUCT BANK)(6 CONDUIT)	900.640				