

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES											TOTALS			DESCRIPTIONS						
ROADWAY	TRAINING	SUPER-STRUCTURE		SUB-STRUCTURE		APPROACH SLABS		EROSION CONTROL		FULL C.E. ITEMS	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
50													50		LF	REMOVING AND RESETING FENCE	620.50			
640													640		LF	SNOW FENCE (MOD. - PDF)	620.70			
458													458		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21			
4													4		EACH	ENERGY ABSORPTION ATTENUATOR (MOD. - SAND-FILLED PLASTIC BARREL)	621.56			
4													4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60			
4													4		EACH	GUARD RAIL APPR. SECTION,NETC 2 RAIL	621.72			
530													530		LF	REMOVL AND DISP OF GUARD RAIL	621.80			
860													860		LF	TEMPORARY TRAFFIC BARRIER	621.90			
80													80		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
240													240		HR	FLAGGERS	630.15			
										1			1		LS	FIELD OFFICE-ENGINEERS	631.10			
										1			1		LS	TESTING EQUIPMENT - CONCRETE	631.16			
										1			1		LS	TESTING EQUIPMENT - BITUMNOUS	631.17			
										1			1		LS	TESTING EQUIPMENT - PROTECTIVE COATNGS	631.18			
										1			1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
	520												520		HR	EMPLOYEE TRAINEESHIP	634.10			
1													1		LS	MOBILIZATION / DEMOBILIZATION	635.11			
1													1		LS	TRAFFIC CONTROL	641.10			
1100													1100		LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40			
1100													1100		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41			
475													475		LF	TEMPORARY 4" WHITE LINE (TAPE, TYPE II)	646.60			
25													25		LF	TEMPORARY 24" STOP BAR (TAPE, TYPE II)	646.66			
410													410		SF	REMOVAL OF EXISTNG PAVEMENT MARKNGS	646.85			
								20					20		SY	GEOTEXTILE UNDER STONE FILL	649.31			
								390					390		SY	GEOTEXTILE FOR SILT FENCE	649.51			
								10					10		LB	SEED	651.15			
								10					10		LB	SEED-WINTER RYE	651.17			
								50					50		LB	FERTILIZER	651.18			
								0.25					0.25		TON	AGRICULTURAL LIMESTONE	651.20			
								0.25					0.25		TON	HAYMULCH	651.25			
								40					40		CY	TOPSOIL	651.35			
								1					1		LS	EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.10			
								50					50		HR	MONITORNG EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.20			
								1					1		LU	MAINTENANCE OF EROSION PREVENTION AND SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30			
								15					15		SY	EROSION MATTING	654.10			
18													18		SF	TRAFFIC SIGNS, TYPE A	675.20			
																*** BEGIN SIGN POST OPTIONS ***				
26													26		LF	FLANGED CHANNEL SIGN POST	675.301			
26													26		LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341			
																*** END SIGN POST OPTIONS ***				
3													3		EACH	REMOVING SIGNS	675.50			
1													1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40			
1													1		EACH	TEMPORARY DETECTOR	678.42			

PROJECT NAME: MONTGOMERY
PROJECT NUMBER: BHF 0283(8)S
FILE NAME: /98c316/sc316qnt.xls PLOT DATE: 5/25/2004
PROJECT LEADER: R. WHITCOMB DRAWN BY: J. GILMORE
DESIGNED BY: STRUCTURES CHECKED BY: C. CARLSON
QUANTITY SHEET #2 SHEET 4 OF 45