ITEM DETAIL SUMMARY SHEET 3

VAOT Metric

LOCATION			GUARDRAIL									MISCELLANEOUS							REMARKS
			616.35	621.17	621.20	621.20	621.505	621.505	621.60	621.65	621.81	203.15	203.16	301.28	616.28	616.47	618.10	618.30	
STATION	STATION	POS.	TREATED TIMBER CURB	CABLE G.R. (MOD.)	STEEL BEAM G.R.	2.4 m STEEL BEAM G.R. (MOD.)	MANUF. TERM. SECTION	MANUFACTURED TERM. SECTION (FLARED)	ANCH. SBGR	ANCH. CABLE G.R.	REMOVE & DISP. G.R.	COMMON EXCAVATION	SOLID ROCK EXCAVATION	SUBBASE OF CRUSHED GRAVEL	CAST IN PLACE PCC CURB TYPE B	BITUMINOUS CONCRETE GUTTERS	P.C.C. SIDEWALK 125 mm (MOD.)	DETECT. WARNING SURFACE	
			M	M	M	M	EA	EA	EA	EA	M	CM	CM	T	M	T	SM	SM	
BARRE CITY																			
U.S. ROUTE 302																			
4+310.5	4+361.0	RT										27.8	18.7	65.7		2.0	85.9		CONSTRUCT NEW SIDEWALK. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS. NON GOVERNMENT PARTICIPATING.
4+319.7		LT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+332.0		LT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+378.0	4+414.0	RT										19.8	13.3	46.8		1.5	61.2		CONSTRUCT NEW SIDEWALK. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS. NON GOVERNMENT PARTICIPATING.
4+380.5	4+417.0	LT										20.1	13.5	47.5		1.5	62.1		CONSTRUCT NEW SIDEWALK. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS. NON GOVERNMENT PARTICIPATING.
4+420.0		LT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+431.5		LT										4.3	2.8	6.0		0.1	13.6	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 6. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+432.0	4+470.0	RT										20.9	14.1	49.4		1.5	64.6		CONSTRUCT NEW SIDEWALK. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS. NON GOVERNMENT PARTICIPATING.
4+433.5	4+473.5	LT										22.0	14.8	52.0		1.6	68.0		CONSTRUCT NEW SIDEWALK. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS. NON GOVERNMENT PARTICIPATING.
4+473.0		RT										4.3	2.8	6.0		0.1	13.6	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 6. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+476.5		LT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+497.6		LT										4.3	2.8	6.0		0.1	13.6	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 6. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+498.2		RT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+557.0		LT										4.3	2.8	6.0		0.1	13.6	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 6. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+560.0		RT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+571.2		LT										4.3	2.8	6.0		0.1	13.6	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 6. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+577.0		RT										2.5	1.7	4.0		0.1	7.7	0.9	SEE STD. SHT. C-3A & C-3B. CONSTRUCT SIDEWALK RAMP, TYPE 1. SEE SHEET 31 OF 32 FOR SIDEWALK DETAILS.
4+655.0	4+690.0	LT														9.7			
4+807.1	4+837.1	RT		30						2	44								SEE VAOT STANDARD SHEETS G-6-1M AND G-6-2M. PROVIDE ANCHORS AT STA. 4+807.1 AND STA. 4+837.1.
4+870.0	4+900.0	RT	30																
4+900.0	4+903.0	RT														0.6			
4+905.0	4+960.0	RT	55																
4+960.0	4+962.0	RT														0.4			
5+006.0	5+066.7	RT				34.2	1	1			60								INSTALL NEW MANUFACTURED TERMINAL SECTION TO NEW RAIL AT STA. 5+021.2. INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) TO NEW RAIL AT STA. 5+055.4.
5+239.5	5+478.9	RT				228.0		1	1		174								INSTALL NEW MANUFACTURED TERMINAL SECTION TO NEW RAIL AT STA. 5+250.9. INSTALL ANCHOR FOR STEEL BEAM GUARDRAIL AT STA. 5+478.0.
SHEET SUBTOTAL			85	30		262.2	1	2	1	2	278	39.0/110.6	25.9/74.4	58.0/261.4		20	121.9/341.8	10.8	ROADWAY/NON GOVERNMENT PARTICIPATING
SHEET 6 SUBTOTAL			-	-		-	-	-	-	-	-	53.0/91.9	34.8/61.8	76.0/217.3		8.2	166.8/284.0	12.6	
SHEET 7 SUBTOTAL			-	-		-	-	-	-	-	-	61.6/214.7	40.4/144.5	88.0/509.3		17.2	194.0/613.3	14.4	
ROUNDING			5	5		3.8	-	-	-	-	22	8.4/20.8	4.9/13.3	20/40		2.6	23.3/54.9	2.2	
TOTAL			90	35		266	1	2	1	2	300	162/438	106/294	242/1028		48	506/1294	40	

DATUM
VERTICAL N/A
HORIZONTAL N/A

ITEM DETAIL SUMMARY SHEET # 3

SURVEYED BY N/A DATE N/A
DRAWN BY C.A.K. DATE 2/02
SQUAD LEADER D.E.G.
DESIGN FILE NO. /pave/98d086/zd086.dgn
IPARM FILE zd0861d3.1 DATE PLOTTED 25-APR-2006 14
PROJ. NAME BARRE CITY
PROJ. NO. ST-STP 2102(1)S
SHEET 8 OF 32 SHEETS