QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL C.E.	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	-	-	1	1	EA	THINNING AND TRIMMING	201.31	-
-	-	-	5	5	CY	COMMON EXCAVATION	203.15	3.0
-	-	-	535	535	CY	EARTH BORROW	203.30	2.6
-	-	-	1	1	CY	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	-
-	-	-	170,100	170,100	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	73
-	-	-	50,000	50,000	LF	MILLED RUMBLE STRIPS	213.10	465.2
-	-	-	8	8	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	0.5
-	-	-	1345	1345	TON	AGGREGATE SHOULDERS (MOD.)	402.12	9.3
-	-	-	430	430	CWT	EMULSIFIED ASPHALT	404.65	3
-	-	-	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
-	-	-	23,700	23,700	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	223
-	-	100	-	100	LF	BRIDGE EXPANSION JOINT (ASPHATIC PLUG)	516.10	10
-	-	100	-	100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL W/ COARSE AGGREGATE	580.20	EST.
-	-	-	74	74	EA	REHABING DI, CB OR MH, CLASS I	604.412	-
-	-	-	200	200	HR	ALL PURPOSE EXCAVATOR RENTAL TYPE I	608.25	EST.
-	-	-	120	120	HR	POWER BROOM RENTAL	608.30	EST.
-	-	-	200	200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
-	-	-	200	200	HR	TRUCK RENTAL	608.37	EST.
-	-	-	10	10	MGAL	DUST CONTROL WITH WATER	609.10	EST.
-	-	-	20	20	CY	STONE FILL, TYPE I	613.10	5
-	-	-	60	60	LF	CAST-IN-PLACE CEMENT CONCRETE CURB TYPE B	616.28	10
-	-	-	2	2	TON	BITUMINOUS CONCRETE CURB, TYPE B	616.31	0.5
-	-	-	800	800	LF	TREATED TIMBER CURB	616.35	16
-	-	-	2	2	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1
-	-	-	20	20	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 IN	618.10	3
-	-	-	6	6	SY	DETECTABLE WARNING SURFACE	618.30	0.5
-	-	-	105	105	EA	YIELDING MARKER POSTS	619.17	EST.
-	-	-	7875	7875	LF	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	-
-	-	-	23	23	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
-	-	-	14	14	EA	TRAILING END TERMINAL	621.52	-
-	-	-	1	1	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
-	-	-	163.8	163.8	LF	ALUMINUM APPROACH RAILING	621.74	-
-	-	-	7641	7641	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
-	-	-	1350	1350	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
-	-	-	1925	1925	HR	FLAGGERS	630.15	EST.
1	-	-	-	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
1	-	-	-	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
1	-	-	-	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BITUMINOUS PAVEMENT
163840	SY	MAINLINE
4066	SY	SIDE ROADS
1630	SY	REST AREA
491	SY	DRIVEWAYS
73	SY	ROUNDING
170,100	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
4572	TON	LEVELING COURSE (TYPE IVS)
18311	TON	WEARING COURSE (TYPE IIIS)
78	TON	WEARING COURSE (TYPE IVS)
452	TON	SIDE ROADS
9	TON	REST AREA
55	TON	DRIVES
223	TON	ROUNDING
23700	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(1)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.

PLOT DATE: 12-MAR-2007 11:27
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.