QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL C.E.	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			1	-	-	-	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
			-	520	-	-	520	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
			-	-	-	1	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
			-	-	-	1	1	LS	TRAFFIC CONTROL	641.10	-
			-	-	-	1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
			-	-	-	4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST.
			-	-	-	9400	9400	LF	DURABLE 4" WHITE LINE (MOD.)(RETROREFLECTIVITY/INLAID)	646.40	35.2
			-	-	-	9900	9900	LF	DURABLE 4" YELLOW LINE (MOD.)(RETROREFLECTIVITY/INLAID)	646.41	61.1
			-	-	-	49100	49100	LF	DURABLE 6" WHITE LINE (MOD.)(RETROREFLECTIVITY/INLAID)	646.414	469.6
			-	-	-	36600	36600	LF	DURABLE 6" YELLOW LINE (MOD.)(RETROREFLECTIVITY/INLAID)	646.415	341.1
			-	-	-	590	590	LF	DURABLE 8" YELLOW LINE (MOD.)(RETROREFLECTIVITY/INLAID)	646.43	4.6
			-	-	-	1015	1015	LF	DURABLE 12" WHITE LINE (MOD.)(RETROREFLECTIVITY/INLAID)	646.44	8.4
			-	-	-	650	650	LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46	4
			-	-	-	384	384	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	-
			-	-	-	225	225	LF	DURABLE CROSSWALK MARKINGS / DIAGONAL LINES (MOD.) (THERMOPLASTIC)	646.51	5
			-	-	-	18750	18750	LF	TEMPORARY 4" WHITE LINE (PAINT)	646.60	20.4
			-	-	-	19700	19700	LF	TEMPORARY 4" YELLOW LINE (PAINT)	646.61	22.2
			-	-	-	97300	97300	LF	TEMPORARY 6" WHITE LINE (PAINT)	646.614	39.2
			-	-	-	72550	72550	LF	TEMPORARY 6" YELLOW LINE (PAINT)	646.615	32.2
			-	-	-	2050	2050	LF	TEMPORARY 12" WHITE LINE (PAINT)	646.64	36.8
			-	-	-	1300	1300	LF	TEMPORARY 24" STOP BAR (PAINT)	646.66	8
			-	-	-	349	349	EA	TEMPORARY LETTER OR SYMBOL (PAINT)	646.70	-
			-	-	-	445	445	LF	TEMPORARY CROSSWALK MARKINGS / DIAGONAL LINES (MOD.) (PAINT)	646.71	5
			-	-	-	3058	3058	EA	LINE STRIPING TARGETS	646.76	EST.
			-	-	-	10100	10100	LF	PAINTED CURB	646.81	16
			-	-	-	80	80	SY	GEOTEXTILE UNDER STONE FILL	649.31	2
			-	-	-	100	100	LB	SEED	651.15	EST.
			-	-	-	250	250	LB	FERTILIZER	651.18	EST.
			-	-	-	1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
			-	-	-	1	1	TON	HAY MULCH	651.25	EST.
			-	-	-	150	150	CY	TOPSOIL	651.35	EST.
			-	-	-	85	85	SY	EROSION MATTING	654.10	3

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(1)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.

PLOT DATE: 12-MAR-2007 11:27
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.