STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																							
WALLINGFORD: 332+25.0, LT	NORTH END DR NEW		48	12	4.00		⊥				1			X 13'		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ARE ASSOCIATED WITH THIS BRACKET ARE SUBSIDIARY TO THE SIGN POST.	-	-
	STOP 0070 1125 0629	1 1	30 6	30 10	6.25 0.42																											BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
332+69.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X 13.66'	X			X															SIGN ID CODE VR-017		E-141
332+94 LT	R R		36	36	9.00						1			X 14'																					
333+18.0, RT	NORTH NORTH	1 1	24 24	12 12	2.00 2.00						2			X 33'																		X	SIGN ID CODE M3-1 SIGN ID CODE M3-1		E-136B E-136A
	VERMONT 7B 7	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE MI-5 SIGN ID CODE MI-4		E-136B E-136A
	← ↑	1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-3		E-136B E-136A
333+23.0, LT	35	1	36	36	9.00						2			X 31.42'																			SIGN ID CODE W3-5	78	
334+01.0, LT	CLARENDON RD						1				1			X 15'		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ARE ASSOCIATED WITH THIS BRACKET ARE SUBSIDIARY TO THE SIGN POST.	-	-
	STOP 0140 1125 0633	1 1	30 6	30 10	6.25 0.42																											BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
334+43.0, LT	SOUTH NORTH	1 1	24 24	12 12	2.00 2.00						2			X 31'																		X	SIGN ID CODE M3-3 SIGN ID CODE M3-1		E-136A E-136B
	7 VERMONT 7B	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE MI-4 SIGN ID CODE MI-5		E-136A E-136B
	↑ →	1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-3 SIGN ID CODE M6-1		E-136A E-136B
					73.1							FT	FT	FT 84 (42.0)	FT - (14.0)	FT - (28.0)	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												151.08																							
				TOTALS	SF 60.1	SF	EA. ~~2~~ 1	SF				FT 84 (42.0)			FT - (42.0)					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(1)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:30
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 47 OF 95