STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																									
WALLINGFORD: 344+22.0, LT		1 1	36 36	48 36	12.00 9.00		4				2		+28 LF	30.17′ X																				BACK TO BACK SIGN ID CODE R4-7 SIGN ID CODE W6-3		E-144 E-151
FIXED SIGN: 4 REMOVAL 4 SALVAGE 28 LF POSTS		1 1	18 18	18 18	2.25 2.25																													BACK TO BACK SIGN ID CODE OM1-1 SIGN ID CODE OM1-1		E-150 E-150
344+78.0, LT	DO NOT ENTER / SPEED LIMIT 45	1 1	36 36	36 48	9.00 12.00						2			X 30.5′																				BACK TO BACK SIGN ID CODE R5-1 SIGN ID CODE R2-1		E-143 E-142
344+78.0, RT	SPEED LIMIT 55	1	36	48	12.00						2			X 30.83′																				SIGN ID CODE R2-1		E-142
346+78.0, LT	WRONG WAY	1	36	24	6.00						1			X 14′		X		X																SIGN ID CODE R5-1A		E-143
346+78.0, LT	WRONG WAY	1	36	24	6.00						1			X		X		X																SIGN ID CODE R5-1A		E-143
346+78.0, RT	NORTH	1	30	15	3.13						1			X 16.42′			X	X																SIGN ID CODE M3-1		E-136A
	7	1	36	36	9.00																													SIGN ID CODE M1-4		E-136A
348+48.0, RT	0070 1125 0660	1	6	10	0.42						1	X 10′			X			X																SIGN ID CODE VD-700		E-138
351+31.0, RT	WEATHER INFO TUNE RADIO TO 1380 97.1 FM	1	132	84		77.00					2												2											SIGN ID CODE DI2-1		E-131
353+74.0, RT	BRIDGE 86-N US 7	1	6	8	0.33						1	X 9.42′			X			X																SIGN ID CODE VD-701		E-134
354+73.0, RT	EMERGENCY STOPPING ONLY	1	30	24	5.00						1			X 14′		X		X																SIGN ID CODE R8-7		E-142
358+05.0, RT	Clarendon 2 Rutland 9	1	120	60		50.00					2												2		239.22 ~~296.1~~								SIGN ID CODE R1-1	81	
							4					FT - (28.0)	FT	FT 84 (56.0) 183.34′	FT - (28.0)	FT - (42.0)	FT - (14.0)		EA	LB	LB	LB		LB	LB ~~296.1~~ 239.22	LB	LB 534.21 ~~551.9~~							
TOTALS		SF 88.38	SF 127.00	EA.	SF							FT 84 (84.0)			FT - (84.0)						LB			EA. 4		LB 773.43 ~~860.8~~			EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(1)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:31
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 49 OF 95