STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																							
CLARENDON: 66+00.0, RT	NORTH / NEXT RIGHT / Clarendon / NEXT LEFT	1	138	126		120.75					2											2				507.4 ~~556.3~~							79	
	FIXED SIGN: LOCATION INCORRECT I REMOVAL/I SALVAGE																																		
68+00.0, RT	BRIDGE 90-N US 7	1	6	8	0.33						1	X 8.5			X			X															SIGN ID CODE VD-701		E-134
68+24.0, RT		1	12	36	3.00						1			X	X			X															SIGN ID CODE OM-3L		E-107
68+24.0, LT		1	12	36	3.00		1				1			X	X			X															SIGN ID CODE OM-3R		E-107
71+40.0, RT	JCT	1	21	15	2.19						1			X 15.5		X		X															SIGN ID CODE M2-1		E-136B
	VERMONT 7B	1	36	36	9.00																												SIGN ID CODE M1-5		E-136B
73+70.0, LT	ONLY ONLY WRONG WAY	1 1	60 36	30 24	12.50 6.00						2			X 29.58		X		X															BACK TO BACK SIGN ID CODE VR-941 SIGN ID CODE R5-1A		E-145A E-143
73+70.0, RT	ONLY ONLY WRONG WAY	1 1	60 36	30 24	12.50 6.00						2			X 30.16		X		X															BACK TO BACK SIGN ID CODE VR-941 SIGN ID CODE R5-1A		E-145A E-143
73+92.0, RT	0070 1105 0140	1	6	10	0.42						1	X 9			X			X															SIGN ID CODE VD-700		E-138
76+00.0, LT	DO NOT ENTER	1	36	36	9.00						1			X 15.25			X	X															SIGN ID CODE R5-1		E-143
76+00.0, RT	DO NOT ENTER	1	36	36	9.00						1			X 16.33			X	X															SIGN ID CODE R5-1		E-143
76+15.0, LT	ONE WAY ONE WAY	1 1	36 36	12 12	3.00 3.00						1			X 13			X	X															BACK TO BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
	STOP	1	30	30	6.25																												SIGN ID CODE R1-1		E-143
												FT - (28.0)	FT	FT - (98.0)	FT - (56.0)	FT - (70.0)	FT 42 (-)		EA	LB	LB	LB		LB	LB	LB	LB 507.4 ~~556.3~~							
												137.32																							
	TOTALS		SF 85.19	SF 120.75	EA. 1	SF						FT - (126.0)			FT 42 (126.0)					LB		EA. 2		LB 507.4 ~~556.3~~			EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(1)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:31
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 54 OF 95