STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																							
CLARENDON: I58+40.0, RT	0070 1105 0300	1	6	10	0.42						1	X 9.17			X			X																SIGN ID CODE VD-700		E-138
162+10.0 RT		1	24	24	4																														
162+10.0, RT	NO3 SOUTH Ludlow NEXT RIGHT	1	126.0	138.0 ~~108.0~~		103.50					2											2				604.7 ~~608.8~~								80	
168+96.0, RT	0070 1105 0320	1	6	10	0.42						1	X 9			X																			SIGN ID CODE VD-700		E-138
170+76.0, RT	BRIDGE 91-N US 7	1	6	8	0.33						1	X 9			X			X																SIGN ID CODE VD-701		E-134
175+44.0, RT	NORTH SOUTH	1 1	30 30	15 15	3.13 3.13						1											1		127.5 ~~135.0~~								X	SIGN ID CODE M3-1 SIGN ID CODE M3-3		E-136A E-136B
	7 VERMONT 103	1	36 45	36 36	9.00 11.25																												SIGN ID CODE M1-4 SIGN ID CODE M1-5		E-136A E-136B
		1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-3 SIGN ID CODE M6-1		E-136A E-136B
175+68.0, LT		1	18	18	2.25						1	X 9.5			X			X																SIGN ID CODE OM1-1		E-150
176+29.00, RT		1	36	48	12.00						2			X 28.25																				SIGN ID CODE R4-7		E-144
		1 1	18 18	18 18	2.25 2.25																												BACK TO BACK SIGN ID CODE OM1-1 SIGN ID CODE OM1-1		E-150 E-150
176+45.0, LT		1	18	18	2.25						1	X 9.42			X			X																SIGN ID CODE OM1-1		E-150
176+58.0, RT	ONE WAY ONE WAY	1 1	36 36	12 12	3.00 3.00						1			X 13.17		X		X															BACK TO BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
	DIVIDED HIGHWAY 0070 1105 0115	1 1	24 6	18 10	3.00 0.42																												BACK TO BACK SIGN ID CODE R6-3 SIGN ID CODE VD-700	78	E-138
177+50.0, RT		1	36	36	9.00						2			X 32.25																				SIGN ID CODE W4-1		E-150
					75.48							FT - (70.0)	FT	FT 56 (14.0)	FT - (70.0)	FT - (14.0)	FT		EA	LB	LB	LB		LB	LB ~~135.0~~	LB	LB ~~608.8~~							
												119.76												732.2										
	TOTALS				SF ~~71.48~~	SF 103.50	EA.	SF				FT 56 (84.0)			FT - (84.0)					LB			EA. 3	LB ~~743.8~~				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(1)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:32
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 59 OF 95