STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 16

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS | | | NEW & SALVAGED SIGNS | | | | EXIST POST | | NEW SIGN POSTS | | | | | | | | | | | | | | | | | | | REMARKS | SIGN DETAIL | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | EA | WIDTH (In) | HEIGHT (In) | "A" | "B" | SALV SIGN | SALV TIS | RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL lb/ft | | | SQUARE STEEL (in) lb/ft | | | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft | | | TUBULAR STEEL Ø (in) lb/ft | | | | | W-SHAPE STEEL FTG. SIZE | | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | | DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | 1.75 | 2.0 | 2.5 | | | 3.0 | 4.0 | 4.0 MOD | FOUND-ATION | 3.0 | 3.5 | 4.0 | 5.0 | 24" | 24" | | | | | |
| | | | | | | | | | | | | 1.12 | 2.0 | 3.0 | 1.88 | 2.16 | 3.35 | | | 1.3 | 1.7 | 1.7 | | 7.6 | 9.0 | 10.8 | 14.6 | | | | | | | |
| | | | | | | | | | | | | OPTION ITEMS ( ) | | | | | | | | | | | | | | | | | | | | | | |
| CLARENDON: 201+33.0, RT | SPEED LIMIT 55 | 1 | 36 | 48 | 12.00 | | | | | | 2 | | | X 33.42 | | | | | | | | | | | | | | | | | | SIGN ID CODE R2-1 | | E-142 |
| | EMERGENCY STOPPING ONLY | 1 | 30 | 24 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE R8-7 | | E-142 |
| 210+22.0, RT | BRIDGE 92-N US 7 | 1 | 6 | 8 | 0.33 | | | | | | 1 | X 8.33 | | | X | | | X | | | | | | | | | | | | | | SIGN ID CODE VD-701 | | E-134 |
| 211+20.0, RT | 0070 1105 0400 | 1 | 6 | 10 | 0.42 | | | | | | 1 | X 8.33 | | | X | | | X | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 211+60.0, RT | N Clarendon 1 Rutland 3 | 1 | 144 | 60 | | 60.00 | | | | | 2 | | | | | | | | | | | | 2 | | | 344.7 ~~347.8~~ | | | | | | | 80 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 221+76.0, RT | 0070 1105 0420 | 1 | 6 | 10 | 0.42 | | | | | | 1 | X 8.83 | | | X | | | X | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 232+32.0, RT | 0070 1105 0440 | 1 | 6 | 10 | 0.42 | | | | | | 1 | X 8.42 | | | X | | | X | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| 242+00.0, RT | JCT | 1 | 21 | 15 | 2.19 | | | | | | ~~2~~ 1 | | | X 16.75 | | X | | X | | | | | | | | | | | | | | SIGN ID CODE M2-1 | | E-136B |
| | VERMONT 7B | 1 | 36 | 36 | 9.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE MI-5 | | E-136B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 242+88.0, RT | 0070 1105 0460 | 1 | 6 | 10 | 0.42 | | | | | | 1 | X 9.5 | | | X | | | X | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| 244+85.0, RT | ← N. CLARENDON | | | | | | 1 | | | | 2 | | | X 26 | | | | | | | | | | | | | | | | | | SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ARE ASSOCIATED WITH THIS BRACKET ARE SUBSIDIARY TO THE SIGN POST. | - | - |
| 247+15.0, LT | LEFT LANE MUST TURN LEFT | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | X 14 | | X | | X | | | | | | | | | | | | | | SIGN ID CODE R3-7L | | E-140 |
| | | | | | | | | | | | | FT - (70.0) | FT | FT 56 (42.0) | FT - (70.0) | FT - (42.0) | FT | | EA | LB | LB 33.2 | LB | | LB | LB | LB 347.8 | LB | | | | | | | |
| | | | | | | | | | | | | 133.58 | | | | | | | | | | | | | | | | 344.7 | | | | | | |
| **TOTALS** | | SF 36.45 | SF 60.00 | EA. 1 | SF | | | | | | | FT 56 (112.0) | | | FT - (112.0) | | | | | LB 33.2 | | | EA. 2 | LB 347.8 | | | | EA. | EA. | LB | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(I)S

FILE NAME: p99bl66.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:32
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 61 OF 95