STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 20

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS ( )																									
CLARENDON: 274+20.0, LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25						2			X																					E-140
		1	36	48	12.00									29																					E-144
		1	18	18	2.25																												SIGN ID CODE OMI-1		E-150
274+56.0, RT	0070 1105 0520	1	6	10	0.42						1	X 8.16			X			X															SIGN ID CODE VD-700		E-138
279+90.0, RT	BRIDGE 95-N US 7	1	6	8	0.33						1	X 8.16			X			X															SIGN ID CODE VD-701		E-134
280+00.0, RT	SHOULDER NARROWS	1	36	36	9.00						2			X 30																			SIGN ID CODE VW-619		E-151
285+12.0, RT	0070 1105 0540	1	6	10	0.42						1	X 9.33			X			X															SIGN ID CODE VD-700		E-138
286+50.0, RT	SPEED LIMIT 45	1	36	36	9.00						2			X 29																			SIGN ID CODE W3-5	78	
287+67.0, LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25						1			X 13		X		X															SIGN ID CODE R3-7L		E-140
288+00.0, RT	BRIDGE 96-N US 7	1	6	8	0.33						1	X 8.5			X			X															SIGN ID CODE VD-701		E-134
	FIXED SIGN: LOCACTION INCORRECT REMOVAL/ISALVAGE																																		
288+01.0, RT		1	12	36	3.00		1				1			X 12.50				X															SIGN ID CODE OM-3L		E-107
							1					FT - (56.0)	FT	FT 84 (28.0)	FT - (56.0)	FT - (28.0)	FT		EA	LB	LB	LB		LB	LB	LB	LB							
												147.65																								
	TOTALS	SF 49.25	SF	EA.	SF							FT 84 (84.0)			FT - (84.0)					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(I)S

FILE NAME: p99bl66.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:32
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 65 OF 95