STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS ( )																									
RUTLAND TOWN: I8+43.0, RT		I	I8	I8	2.25						I	X 9.50			X			X															SIGN ID CODE OMI-1		E-150
I8+43.0, RT	36 X 36 X 36	I			3.90						I			X 13	X			X															SIGN ID CODE RI-2		E-146
I8+56.0, LT		I	24	30	5.00						I			X 13		X			X														SIGN ID CODE R4-7		E-144
		I	I8	I8	2.25																												SIGN ID CODE OMI-1		E-150
I8+58.0, RT	WEST EAST NORTH	I I I	24 24 24	I2 I2 I2	2.00 2.00 2.00						2												2	I7I.0 ~~212.8~~								X	SIGN ID CODE M3-4 SIGN ID CODE M3-2 SIGN ID CODE M3-1		E-136A E-136A E-136A
	4 4 7	I I I	24 24 24	24 24 24	4.00 4.00 4.00																												SIGN ID CODE MI-4 SIGN ID CODE MI-4 SIGN ID CODE MI-4		E-136A E-136A E-136A
		I I I	2I 2I 2I	I5 I5 I5	2.19 2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-3 SIGN ID CODE M6-3		E-136A E-136A E-136A
I9+I0.0 RT	LEFT LANE MUST TURN LEFT		30	30	625																														
I9+I0.0, RT		I	24	30	5.00						I			X 13		X		X															SIGN ID CODE R4-7		E-144
		I	I8	I8	2.25																												SIGN ID CODE OMI-1		E-150
I9+56.0, RT		I	I8	I8	2.25						I	X 9.50			X			X															SIGN ID CODE OMI-1		E-150
I9+6I.0, RT	36 X 36 X 36	I			3.90						I			X 13	X			X															SIGN ID CODE RI-2		E-146
I9+95.0, RT	DIAMOND RUN MALL PLACE						I				2		X 24.25																					SALVAGED SIGN SHALL BE MOUNTED ON NEW POST.	-	-
					57.62							FT - (28.0)	FT 28.0 (-)	FT - (56.0)	FT - (56.0)	FT - (28.0)	FT		EA I	LB	LB	LB		LB 212.8	LB	LB	LB								
												95.25												171.0											
TOTALS			SF ~~51.37~~	SF	EA. I	SF			FT 28 (84.0)						FT - (84.0)					LB			EA. 2	LB 212.8				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(I)S

FILE NAME: p99bI66.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: I2-MAR-2007 II:33
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 69 OF 95