STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 32

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																									
	SHEET 46 SUBTOTALS			38.52	~~34.52~~	-	0 ~~1~~					- (28.0)	107.48 (-)	- (84.0)	- (42.0)	- (70.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 47 SUBTOTALS			73.1	~~60.10~~	-	1 ~~2~~					- (-)	151.08 (-)	84.0 (42.0)	- (14.0)	- (28.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 48 SUBTOTALS				42.52	-	-					- (42.0)	135.25 (-)	- (98.0)	- (42.0)	- (84.0)	- (14.0)		-		-		-	-	-	-	-							
	SHEET 49 SUBTOTALS				88.38	127.00	4 -					- (28.0)	183.34 - (-)	84.0 (56.0)	- (28.0)	- (42.0)	- (14.0)		-		-		4	-	239.22 ~~296.1~~	-	534.21 ~~551.9~~							
	SHEET 50 SUBTOTALS				9.60	-	-					- (98.0)	91.24 (-)	- (14.0)	- (98.0)	- (14.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 51 SUBTOTALS				89.92	-	-					- (14.0)	178.58 (-)	84.0 (-)	- (14.0)	- (-)	70.0 (-)		-		-		-	-	-	-	-							
	SHEET 52 SUBTOTALS			67.00	~~70.00~~	64.00	2 ~~1~~					- (28.0)	176.47 (-)	56.0 (42.0)	- (42.0)	- (14.0)	42.0 (14.0)		-		-		2	-	-	-	~~705.2~~ 592.5							
	SHEET 53 SUBTOTALS				57.34	-	-					- (14.0)	123.08 (-)	84.0 (-)	- (14.0)	- (-)	14.0 (-)		-		-		-	-	-	-	-							
	SHEET 54 SUBTOTALS				85.19	120.75	1 -					- (28.0)	137.32 (-)	- (98.0)	- (56.0)	- (70.0)	42.0 (-)		-		-		2	-	-	-	~~556.3~~ 507.4							
	SHEET 55 SUBTOTALS				84.11	57.50	1 -					- (14.0)	109.08 ~~56.0~~ (28.0)	- (-)	- (28.0)	- (14.0)	14.0 (-)		-		-		3	-	402.4 ~~418.5~~	-	-							
	SHEET 56 SUBTOTALS				22.26	117.50	-					- (42.0)	69.5 (-)	- (14.0)	- (56.0)	- (-)	28.0 (-)		-		-		4	-	~~410.9~~ 511.6	-	-							
	SHEET 57 SUBTOTALS				87.75	42.25	-					- (14.0)	115.58 (-)	84.0 (14.0)	- (14.0)	- (-)	- (14.0)		-		-		2	250.2 ~~103.5~~	-	-	-							
	SHEET 58 SUBTOTALS				26.59	135.25	-					- (28.0)	72.58 (-)	- (42.0)	- (42.0)	- (28.0)	14.0 (-)		-		-		4	-	~~275.4~~ 238.5	~~427.6~~ 402.3	-							
	SHEET 59 SUBTOTALS			75.48	~~71.48~~	103.50	-					- (70.0)	119.76 - (-)	56.0 (14.0)	- (70.0)	- (14.0)	- (-)		-		-		3	-	127.5 ~~135.0~~	-	604.7 ~~608.8~~							
	SHEET 60 SUBTOTALS				46.90	-	1 -					- (28.0)	136.99 (-)	28.0 (14.0)	- (28.0)	- (14.0)	42.0 (-)		-		-		-	-	-	344.7 ~~347.8~~	-							
	SHEET 61 SUBTOTALS				36.45	60.00	1					- (70.0)	133.58 (-)	56.0 (42.0)	- (70.0)	- (42.0)	- (-)		-		-		2	-	-										
	SHEET 62 SUBTOTALS				90.55	-	-					- (14.0)	- (-)	84.0 (14.0)	- (28.0)	- (-)	- (-)		-		-		2	~~159.6~~ 228.0	-	-	-							
	SHEET 63 SUBTOTALS			26.21	~~22.21~~	116.00	-					- (42.0)	108.25 70.82 (-)	~~28.0~~ (14.0)	- (42.0)	- (14.0)	- (-)		-		-		4	219.1 ~~205.2~~	-	441.9 ~~487.1~~	-							
	SHEET 64 SUBTOTALS				71.92	-	1					- (-)	- (28.0)	84.0 (28.0)	- (14.0)	- (42.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 65 SUBTOTALS				49.25	-	1 -					- (56.0)	134.41 147.65	84.0 (28.0)	- (56.0)	- (28.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 66 SUBTOTALS				49.92	68.00	-					- (14.0)	137.0 (-)	112.0 (14.0)	- (14.0)	- (14.0)	- (-)		-		-		2	-	-	~~386.6~~ 353.7	-							
	SHEET 67 SUBTOTALS				56.34	-	1					- (-)	128.83 (28.0)	56.0 (56.0)	- (-)	- (84.0)	- (-)		1		-		-	-	-	-	-							
	SHEET 68 SUBTOTALS				32.67	-	1					- (14.0)	~~28.0~~ (-)	- (56.0)	- (14.0)	- (56.0)	- (-)		1		-		-	-	-	-	-							
	SHEET 69 SUBTOTALS			57.62	~~51.37~~	-	1					95.25 (28.0)	87.0 ~~28.0~~ (-)	- (56.0)	- (56.0)	- (28.0)	- (-)		1		-		2	171.0 ~~212.8~~	-	-	-							
	SHEET 70 SUBTOTALS				40.57	50.00	-					- (14.0)	108.25 (-)	56.0 (42.0)	- (14.0)	- (42.0)	- (-)		1		-		2	-	~~261.9~~ 192.8	-	-							
	SHEET 71 SUBTOTALS				48.92	-	~~1~~ 4					- (14.0)	137.08 ~~28.0~~ (-)	- 98.0	- (14.0)	- (126.0)	- (-)		1		-		-	-	-	-	-							
	SHEET 72 SUBTOTALS				33.09	-	-					- (14.0)	87.75 (-)	- (84.0)	- (14.0)	- (84.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 73 SUBTOTALS			54.5	~~43.50~~	-	-					- (-)	97.0 - (14.0)	- (56.0)	- (-)	- (70.0)	14.0 (-)		-		-		-	-	-	-	-							
	SHEET 74 SUBTOTALS				40.67	-	-					- (-)	81.0 (-)	- (56.0)	- (-)	- (56.0)	14.0 (-)		-		-		-	-	-	-	-							
	SHEET 75 SUBTOTALS				51.00	-	-					- (-)	117.92 - (14.0)	- (112.0)	- (-)	- (126.0)	- (-)		-		-		-	-	-	-	-							
	SHEET 76 SUBTOTALS				11.97	-	-					- (-)	- (-) 25.0	- (28.0)	- (-)	- (28.0)	- (-)		-		-		-	-	-	-	-							
					1646.31		21					FT - (756.0)	FT 112 (140.0)	FT 1120 (1316)	FT - (924.0)	FT - (1232)	FT 294 (56.0)		EA 5		LB		LB 868.3 681.1	LB 1712.05 1797.8	LB 1542.6 1649.1	LB 2240.0 2422.2							
	TOTALS				SF 1607.06	SF 1061.75	EA. 10	SF					FT 1232.0 (2212.0) 3599.12			FT 294.0 (2212.0)						LB		EA. 38	LB 6550.2 *6361.73				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

*SLIGHT ROUNDING DISCREPANCY BETWEEN SIGN SUMMARY & CALCULATION SHEET

PROJECT NAME: WALLINGFORD - RUTLAND TOWN
PROJECT NUMBER: AC NH 2207(I)S

FILE NAME: p99b166.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
PLOT DATE: 12-MAR-2007 11:33
DRAWN BY: M.L.M.
CHECKED BY: D.E.G.
SHEET 77 OF 95