



**HANDWORK DETAILS FOR DRIVES**

VT ROUTE 12

**NOTES:**

1. PAVING LIFT NOT TO EXCEED 2" (50mm)
2. THE COST OF PLACING SUBBASE MATERIAL, CLEANING EXISTING PAVED SURFACES, INCLUDING POWER EQUIPMENT, AND FOR FILLING JOINTS, CRACKS AND HOLES WILL NOT BE PAID DIRECTLY BUT WILL BE CONSIDERED INCIDENTAL TO ITEM 900.675 \*SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)\*.
3. EXCAVATION NEEDED TO ACHIEVE PROPER DRIVE SLOPES WILL NOT BE PAID DIRECTLY BUT WILL BE CONSIDERED INCIDENTAL TO ITEM 900.675 \*SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)\*.

**LEGEND**

 BITUMINOUS PAVEMENT, 900.675 \*SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)\*

STATION	POSITION	QUANTITY (SY)
WORCESTER		
219+96	RT	8.0
233+18	LT	9.2
234+24	RT	9.1
238+50	LT	5.8
242+06	LT	14.6
244+84	LT	7.4
256+29	LT	12.0
257+32	LT	20.0
268+97	RT	6.5
273+51	LT	12.9
274+90	RT	6.5
294+26	LT	12.0
318+75	LT	8.3
321+76	RT	6.5
323+99	LT	7.4
325+23	LT	11.9
329+87	LT	10.9
339+00	RT	7.0
349+64	RT	8.3
369+09	RT	10.1
370+51	LT	10.4
376+25	RT	14.6
391+50	LT	8.1
407+80	LT	7.4
410+93	LT	7.4

STATION	POSITION	QUANTITY (SY)
ELMORE		
11+01	LT	11.1
26+00	LT	14.4
32+52	RT	6.4
57+70	RT	17.9
64+75	RT	8.3
70+85	RT	8.3
76+82	RT	15.6
77+68	LT	26.1
84+54	RT	11.0
97+40	RT	11.0
113+88	RT	8.4
139+85	RT	9.2
151+77	RT	8.3
174+42	LT	10.2
175+77	RT	12.2
179+90	RT	17.6
184+81	LT	13.7
185+46	RT	13.7
	SUBTOTAL	465.7
	ROUNDING	9.3
	TOTAL	475.0

DETAILS ARE NOT TO SCALE

<b>HANDWORK DETAILS FOR DRIVES</b>	PROJECT NAME: WORCESTER-ELMORE	PLOT DATE: 23-SEP-2011 15:24
	PROJECT NUMBER: STP 2209(1)S	DRAWN BY: SJL
	FILE NAME: 99c170.dgn	CHECKED BY: EPD
	PROJECT LEADER: CDL	SHEET 8 OF 36
	DESIGNED BY: SJL	
	PLOT FILE: 99c170_8.i	