QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						3	3	EACH	THINNING AND TRIMMING FOR SIGNS	201.31	EST
						100	100	CY	COMMON EXCAVATION	203.15	-
						2250	2250	CY	EARTH BORROW	203.30	-
						2250	2250	CY	TRENCH EXCAVATION OF EARTH	204.20	160
						1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
						3900	3900	SY	COLD PLANING BITUMINOUS PAVEMENT	210.10	30.89
						14900	14900	TON	SUBBASE OF GRAVEL, FINE GRADED	301.28	185
						126500	126500	SY	RECLAIMED STABILIZED BASE	310.20	325
						2200	2200	TON	AGGREGATE SHOULDERS	402.12	20
						300	300	TON	AGGREGATE SHOULDERS, RAP	402.13	-
						300	300	CWT	EMULSIFIED ASPHALT	404.65	14
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
						35000	35000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	673.04
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
						1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
						1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
						1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					145		145	LF	BRIDGE EXPANSION JOINT, ASPHALT PLUG	516.10	3
					250		250	LF	REMOVAL OF EXISTING RAILING	525.10	-
					250		250	LF	BRIDGE RAILING REPAIR, TYPE II	525.55	-
					35		35	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	5
						330	330	LF	15" CSP .064 (2-2/3 X 1/2)	601.0010	-
						4	4	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
						3750	3750	LF	6 INCH UNDERDRAIN PIPE	605.10	EST
						650	650	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	EST
						18	18	EA	UNDERDRAIN FLUSHING BASIN	605.95	EST
						520	520	HR	POWER GRADER RENTAL	608.15	EST
						1260	1260	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						190	190	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
						90	90	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
						2520	2520	HR	TRUCK RENTAL	608.37	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
3869.11	SY	VT ROUTE 12
30.89	SY	ROUNDING
3900	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
11431.89	TON	TYPE IV
22655.92	TON	TYPE IIS
		PULLOFFS
235.42	TON	TYPE IVS
		LEVELING COURSE
3.73	TON	TYPE IVS
673.04	TON	ROUNDING
35000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WORCESTER-ELMORE
PROJECT NUMBER: STP 2209(I)S

FILE NAME: 99c170.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #1

PLOT DATE: 23-SEP-2011 15:24
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 9 OF 36