QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						520	520	HR	LOADER RENTAL, TYPE I	608.40	EST
						800	800	CY	STONE FILL, TYPE I	613.10	23
						800	800	LF	TREATED TIMBER CURB	616.35	-
						5	5	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	EST
						214	214	EACH	YIELDING MARKER POSTS	619.17	-
						14275	14275	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	19.25
						4550	4550	LF	STEEL BEAM, GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	13.5
						75	75	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	-
						150	150	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2.5
						165	165	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215	-
						87	87	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
						1	1	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	-
						12	12	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
						19107	19107	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
						300	300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
						4500	4500	HR	FLAGGERS	630.15	EST
			1				1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1				1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
				520			520	HR	EMPLOYEE TRAINEESHIP	634.10	-
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						80000	80000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1618
						63000	63000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	1719
						238000	238000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	2853
						187000	187000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	1314
						2100	2100	EA	LINE STRIPING TARGETS	646.76	100
						2400	2400	SY	GEOTEXTILE UNDER STONE FILL	649.31	88
						130	130	LB	SEED	651.15	13.1
						1100	1100	LB	FERTILIZER	651.18	126
						4.5	4.5	TON	AGRICULTURAL LIMESTONE	651.20	0.60
						2	2	TON	HAY MULCH	651.25	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WORCESTER-ELMORE
PROJECT NUMBER: STP 2209(I)S

FILE NAME: 99c170.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #2

PLOT DATE: 23-SEP-2011 15:24
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 10 OF 36