STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET NO. 4

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD. lb/ft 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																								
220+55 LT	STOP 1090 0809 0418	1 1	30 6	30 10	6.25 0.42						1			X		X																		BACK TO BACK		E-143 E-138
220+95 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1			X		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
	SPEED LIMIT 35																																			
BELVIDERE 8+90 LT	STOP 1090 0801 0018	1	6	10	0.42				1																								MOUNT NEW MILE MARKER BACK TO BACK WITH RETAINED STOP SIGN.		E-138
21+48 RT	STOP 1090 0801 0041	1	6	10	0.42				1																								MOUNT NEW MILE MARKER BACK TO BACK WITH RETAINED STOP SIGN.		E-138
50+65 LT	STOP 1090 0801 0096	1	6	10	0.42				1																								MOUNT NEW MILE MARKER BACK TO BACK WITH RETAINED STOP SIGN.		E-138
131+00 RT	NARROW BRIDGE	1	30	30	6.25						1			X		X																				E-154
132+34 LT		1	12	36	3.0						1			X		X																				E-120
132+34 RT		1	12	36	3.0						1			X		X																				E-120
132+90 RT		1	12	36	3.0						1			X		X																				E-120
132+90 LT		1	12	36	3.0						1			X		X																				E-120
133+25 LT	STOP 1090 0801 0253	1	6	10	0.42				1																								MOUNT NEW MILE MARKER BACK TO BACK WITH RETAINED STOP SIGN.		E-138
135+00 LT	NARROW BRIDGE	1	30	30	6.25						1			X		X																				E-154

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

	SF	SF	EA.	SF		FT	FT	FT	FT	FT	FT		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB
SIGN SHEET #1	53.68							~~165~~		~~165~~														
SIGN SHEET #2	70.02		2					~~180~~		~~180~~														
SIGN SHEET #3	65.02		~~13~~					~~165~~		~~165~~														
SIGN SHEET #4	37.85		1					~~120~~		~~120~~														
PROJECT TOTALS	226.57		~~16~~				561.5 ~~630~~			561.5 ~~630~~														

TRAFFIC SIGN SUMMARY SHEET #4

PROJECT: **CAMBRIDGE – BELVIDERE** | PROJECT NO.: **STP 2219(1)S** | DATE: 8-00

DESIGN FILE NAME: p99cl90.dgn
IPARM FILE NAME: p99cl90tss4.i
SURVEYED BY: C.E.A., INC.
SQUAD LEADER: C.E.A., INC.

PLOT DATE: 12-DEC-2008 09:54
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **33** OF **37**