

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES											DETAILED SUMMARY OF QUANTITIES			DETAILED SUMMARY OF QUANTITIES		
	NON-GOV'T PARTICIPATING		GOV'T PARTICIPATING		QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS	
	BRIDGE	ROADWAY	BRIDGE	ROADWAY												
					1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	--							
					1	LS	MOBILIZATION	635.10	--							
					30,480	LF	DURABLE 4" WHITE LINE	646.40	12.0							
					31,360	LF	DURABLE 4" YELLOW LINE	646.41	13.5							
					300	LF	DURABLE 8" WHITE LINE	646.42	14.1							
					780	LF	DURABLE 8" YELLOW LINE	646.43	11.4							
					30	LF	DURABLE 24" STOP BAR	646.46	6.0							
					8	EA	DURABLE LETTER OR SYMBOL	646.50	0.0							
					60,960	LF	TEMPORARY 4" WHITE LINE	646.60	0.0							
					62,720	LF	TEMPORARY 4" YELLOW LINE	646.61	0.0							
					60	LF	TEMPORARY 24" STOP BAR	646.66	0.0							
					16	EA	TEMPORARY LETTER OR SYMBOL	646.70	0.0							
					360	EA	LINE STRIPING TARGETS	646.73	0.3							
					300	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.82	4.2							
					40	lb	SEED	651.15	0.49							
					360	lb	FERTILIZER	651.18	10.8							
					2	t	AGRICULTURAL LIMESTONE	651.20	0.68							
					2	t	HAY MULCH	651.25	0.68							
					900	CY	TOPSOIL	651.35	12.9							
					135	ft ²	TRAFFIC SIGNS, TYPE A	675.20	3.32							
							***** BEGIN OPTION ITEMS *****									
					400	LF	FLANGED CHANNEL SIGN POST	675.301	10.0							
					400	LF	SQUARE TUBE STEEL POSTS AND ANCHORS	675.341	10.0							
							***** END OPTION ITEMS *****									
					11	EA	REMOVING SIGNS	675.50	0.0							
					11	EA	ERECTING SALVAGED SIGNS	675.60	0.0							

PROJECT: DORSET-MT TABOR-DANBY	PROJECT NO.: NH 2132 (1) 5
DESIGN FILE NAME: /pave/93b080a/pb080.dgn IPARM FILE NAME: pb080qs2.i SURVEYED BY: N/A SQUAD LEADER: JAV	PLOT DATE: 13-AUG-1999 SURVEY DATE: N/A DRAWN BY: SJL SHEET: 5 OF 19