COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

DANVILLE-ST. JOHNSBURY NH 2501(I)S				DANVILLE NH 2205(I)S		SUMMARY OF ESTIMATED QUANTITIES			
	NON-FED. PARTIC.	FULL E&C	ROADWAY	FULL E&C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.
			5		10	15	EA	THINNING AND TRIMMING FOR SIGNS	201.31
			-		150	150	CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28
			200		140	340	CY	EARTH BORROW	203.30
			6050		-	6050	LF	SHOULDER BERM REMOVAL	203.40
			0.5		0.5	1.0	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22
			35000		57000	92000	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10
			1900		620	2520	TON	AGGREGATE SHOULDERS, RAP	402.13
			1050		285	1335	CWT	EMULSIFIED ASPHALT	404.65
			0.5		0.5	1.0	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50
			32500		9000	41500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30
			0.5		0.5	1.0	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31
			0.5		0.5	1.0	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32
			0.5		0.5	1.0	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33
			0.5		0.5	1.0	LU	LONGITUDINAL JOINT COMPACTION PAY ADJ. (N.A.B.I.)	490.34
			100		-	100	LF	CLEANING CULVERT PIPE, IN PLACE (0 - 24'' INCL.)	601.995
			100		-	100	LF	CLEANING CULVERT PIPE, IN PLACE (GREATER THAN 24'')	601.996
			10		-	10	EA	CHANGING ELEVATION OF DI, CB OR MH	604.40
			16		1	17	EA	REHABING DI, CB OR MH CLASS I	604.412
			120		40	160	HR	POWER GRADER RENTAL	608.15
			700		60	760	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25
			120		40	160	HR	POWER BROOM RENTAL, TYPE I	608.30
			60		20	80	HR	POWER BROOM RENTAL, TYPE II	608.31
			1400		120	1520	HR	TRUCK RENTAL	608.37
			120		120	240	HR	LOADER RENTAL , TYPE I	608.40
			780		100	880	CY	STONE FILL, TYPE I	613.10
			1900		-	1900	LF	TREATED TIMBER CURB	616.35
			2050		-	2050	LF	REMOVING AND RESETTING CURB	616.40
			70		-	70	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47
			160		7	167	EA	YIELDING MARKER POSTS	619.17
			8300		3900	12200	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20
			1500		-	1500	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8' POSTS	621.205
			35		11	46	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50
			1		1	2	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51
			7		-	7	EA	ANCHOR FOR STEEL BEAM RAIL	621.60
			12.5		-	12.5	LF	REMOVE AND RESET GUARD RAIL	621.75
			50		-	50	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76
			150		-	150	EA	REPLACE GUARDRAIL BEAM UNIT	621.77
			11000		4400	15400	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80

DETAILED SUMMARY OF QUANTITIES
ITEMS
REFER TO SHEETS 9 AND 10 AND SHEETS 28 AND 29 FOR DETAILED INFORMATION RELATING TO EACH INDIVIDUAL PROJECT.

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: DANVILLE
PROJECT NUMBER: NH 2205 (I)S

DANVILLE - ST. JOHNSBURY NH 2501(I)S

FILE NAME: pave/99b162/99b162
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 99B162cqsl.i

PLOT DATE: 16-FEB-2007
DRAWN BY: SJB
CHECKED BY: EPD
SHEET 3 OF 63