QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL E&C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	10	10	EA	THINNING AND TRIMMING FOR SIGNS	201.31	EST
	150	150	CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	9
	140	140	CY	EARTH BORROW	203.30	EST
	0.5	0.5	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
	57000	57000	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	1503.86
	620	620	TON	AGGREGATE SHOULDERS, RAP	402.13	22
	285	285	CWT	EMULSIFIED ASPHALT	404.65	1.7
	0.5	0.5	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
	9000	9000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30	116.92
	0.5	0.5	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	0.5	0.5	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
	0.5	0.5	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
	0.5	0.5	LU	LONGITUDINAL JOINT COMPACTION PAY ADJ. (N.A.B.I.)	490.34	-
	1	1	EA	REHABING DI, CB OR MH CLASS I	604.412	-
	40	40	HR	POWER GRADER RENTAL	608.15	EST
	60	60	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
	40	40	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
	20	20	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
	120	120	HR	TRUCK RENTAL	608.37	EST
	120	120	HR	LOADER RENTAL , TYPE I	608.40	EST
	100	100	CY	STONE FILL, TYPE I	613.10	11
	7	7	EA	YIELDING MARKER POSTS	619.17	-
	3900	3900	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	12.5
	11	11	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
	1	1	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	-
	4400	4400	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	21.5
	1100	1100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
	4350	4350	HR	FLAGGERS	630.15	EST
0.5		0.5	LS	FIELD OFFICE - ENGINEERS	631.10	-
0.5		0.5	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
0.5		0.5	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
	0.5	0.5	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
	0.5	0.5	LS	TRAFFIC CONTROL	641.10	-
	4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS CONCRETE
55496.14	SY	U.S. ROUTE 2
1503.86	SY	ROUNDING
57000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
1560.83	TON	LEVELING COURSE
3718.68	TON	SHOULDER
3603.57	TON	TRAVEL LANE
116.92	TON	ROUNDING
9000.00	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: DANVILLE
PROJECT NUMBER: NH 2205 (I)S

FILE NAME: pave/99b162/99b162
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 99B162qsl.i

PLOT DATE: 12-JAN-2007
DRAWN BY: SJB
CHECKED BY: EPD
SHEET 9 OF 63