STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 147+76.60 RT	0020 0303 0280	1	6	10	0.42						1	X			X																				E-138
STA. 157+19.64 LT	SPEED LIMIT 50	1	24	30	5.00						1			X		X																	R2-1		E-142
STA. 158+38.79 RT	0020 0303 0300	1	6	10	0.42						1	X			X																				E-138
STA. 158+46.52 RT	BRIDGE 93 US 2	1	6	8	0.33						1	X			X																		VD-701		E-134
STA. 158+68.73 LT	BRIDGE 93 US 2	1	6	8	0.33						1	X			X																		VD-701		E-134
STA. 162+32.35 RT	TRUCK LANE 500 FEET	1	24	30	5.00						1			X		X																	R4-6		E-141
STA. 169+04.94 LT	0020 0303 0320	1	6	10	0.42						1	X			X																				E-138
STA. 175+00.00 RT	RIGHT LANE ENDS	1	36	36	9.00						2			X		X																	W9-1R	21	
STA. 178+00.00 RT		1	36	36	9.00						2			X		X																	W4-2		E-151
STA. 179+58.29 RT	0020 0303 0340	1	6	10	0.42						1																								E-138
STA. 183+13.28 RT	HIDDEN DRIVE LEFT	1	30	30	6.25						1			X		X																	VW-054		E-154
STA. 190+02.14 LT	0020 0303 0360	1	6	10	0.42						1	X			X																				E-138
												FT 56.0	FT	FT 105.0	FT 56.0	FT 105.0	FT	FT	EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS			SF 37.01	SF	EA.	SF						FT 161.0			FT 161.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: DANVILLE
PROJECT NUMBER: NH 2205 (1)S

FILE NAME: pave/99b162/99b162
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 99B162ts03.i

PLOT DATE: 12-JAN-2007
DRAWN BY: SJB
CHECKED BY: EPD
SHEET 19 OF 63