STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA. 196+91.83 RT	SPEED LIMIT 40	1	36	36	9.00						2			X		X																	W3-5	21	
STA. 200+60.42 RT	0020 0303 0380	1	6	10	0.42						1	X			X																				E-138
STA. 202+08.81 RT	SPEED LIMIT 40	1	24	30	5.00						1			X		X																	R2-1		E-142
STA. 202+08.81 LT	SPEED LIMIT 50	1	24	30	5.00						1			X		X																	R2-1		E-142
STA. 205+04.75 RT		1	30	30	6.25						1			X		X																	W11-6H (FOLDING SIGN)		E-153
STA. 207+77.84 RT	SPEED LIMIT 30	1	36	36	9.00						2			X		X																	W3-5	21	
STA. 210+80.01 RT	DANVILLE ST JOHNSBURY 7	1	30	18	3.75						1			X		X																			E-128A E-128B
STA. 211+16.79 LT	0020 0303 0400	1	6	10	0.42						1	X			X																				E-138
STA. 212+93.20 LT	SPEED LIMIT 40	1	24	30	5.00						1			X		X																	R2-1		E-142
STA. 213+24.69 RT	SPEED LIMIT 30	1	30	36	7.50						1			X		X																	R2-1		E-142
	SUBTOTAL				51.34							16.0		150.0	16.0	150.0																				
	SHEET 17 TOTAL				86.37		3					16.0		210.0	16.0	210.0																				
	SHEET 18 TOTAL				46.34		2					40.0		120.0	40.0	120.0																				
	SHEET 19 TOTAL				37.01							56.0		105.0	56.0	105.0																				
												FT 128.0	FT	FT 585.0	FT 128.0	FT 585.0	FT	FT	EA	LB	LB	LB		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."	SUBTOTALS				221.06		5																												
	ROUNDING				3.94		--																												
	GRAND TOTALS				SF 225	SF	EA. 5	SF				FT 720			FT 720					LB			EA.	LB				EA.	EA.	LB					

TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: DANVILLE
PROJECT NUMBER: NH 2205 (1)S

FILE NAME: pave/99b162/99b162
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 99B162ts04.1

PLOT DATE: 12-JAN-2007
DRAWN BY: SJB
CHECKED BY: EPD
SHEET 20 OF 63