QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

				NON-FED. PARTIC.	FULL E&C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					0.5		0.5	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
					0.5		0.5	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
						0.5	0.5	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
						0.5	0.5	LS	TRAFFIC CONTROL	641.10	-
						4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						19000	19000	LF	DURABLE 4" WHITE LINE, THERMOPLASTIC	646.402	462
						17500	17500	LF	DURABLE 4" YELLOW LINE, THERMOPLASTIC	646.412	327
						66000	66000	LF	DURABLE 6" WHITE LINE, RECESSED	646.426	606
						55500	55500	LF	DURABLE 6" YELLOW LINE, RECESSED	646.436	585
						2600	2600	LF	DURABLE 12" WHITE LINE, RECESSED	646.466	78
						220	220	LF	DURABLE 12" YELLOW LINE, RECESSED	646.476	5
						330	330	LF	DURABLE 24" STOP BAR, THERMOPLASTIC	646.482	18
						97	97	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
						19000	19000	LF	TEMPORARY 4" WHITE LINE, PAINT	646.602	441
						17500	17500	LF	TEMPORARY 4" YELLOW LINE, PAINT	646.612	297
						115000	115000	LF	TEMPORARY 6" WHITE LINE, PAINT	646.622	1257
						57000	57000	LF	TEMPORARY 6" YELLOW LINE, PAINT	646.632	1392
						2600	2600	LF	TEMPORARY 12" WHITE LINE, PAINT	646.662	78
						220	220	LF	TEMPORARY 12" YELLOW LINE, PAINT	646.672	5
						350	350	LF	TEMPORARY 24" STOP BAR, PAINT	646.682	8
						130	130	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	2
						3300	3300	EA	LINE STRIPING TARGETS	646.76	75
						1800	1800	LF	PAINTED CURB	646.81	45.6
						2150	2150	SY	GEOTEXTILE UNDER STONE FILL	649.31	41
						140	140	LB	SEED	651.15	EST
						1200	1200	LB	FERTILIZER	651.18	EST
						5	5	TON	AGRICULTURAL LIMESTONE	651.20	EST
						5	5	TON	HAY MULCH	651.25	EST
						200	200	CY	TOPSOIL	651.35	EST
						8550	8550	SY	TEMPORARY EROSION MATTING	653.20	155
						940	940	SF	TRAFFIC SIGNS, TYPE A	675.20	17.87
									BEGIN OPTION ITEM		
				90		2310	2400	LF	FLANGED CHANNEL SIGN POST	675.301	35
				90		2310	2400	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	35
									END OPTION ITEM		
						2100	2100	LB	TUBULAR STEEL SIGN POST	675.33	48
						18	18	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	-
						203	203	EA	REMOVING SIGNS	675.50	-
						22	22	EA	ERECTING SALVAGED SIGNS	675.60	-
						43	43	EA	DELINEATORS W/ STEEL POSTS	676.10	-
				64			64	SF	TRAVEL INFORMATION SIGNS	680.20	-
						0.5	0.5	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
						280	280	TON	SPECIAL PROVISION (SUBBASE, RAP)	900.680	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: DANVILLE - ST. JOHNSBURY
PROJECT NUMBER: NH 2501(1)S

FILE NAME: pave/05b034/05b034
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 05b034qs2.1

PLOT DATE: 16-FEB-2007
DRAWN BY: SJB
CHECKED BY: EPD
SHEET 29 OF 63