STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 / lb/ft 1.88	SQUARE STEEL (in) 2.0 / lb/ft 2.16	SQUARE STEEL (in) 2.5 / lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 / lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 / lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD / lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 / lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 / lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 / lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 / lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 388+41.53 LT	STOP; JAMIESON RD; JAMIESON RD; 0020 0303 0734	1 1	30 6	30 10	6.25 0.42		2				1			X		X																	RI-1 MOUNT REF. PLAQUE BACK TO BACK W/ STOP SIGN. MOUNT STREET SIGN OVER STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-143 E-138
STA. 388+66.68 RT	STOP; 0020 0303 0734	1 1	30 6	30 10	6.25 0.42						1			X		X																	RI-1 MOUNT REF. PLAQUE BACK TO BACK W/ STOP SIGN.		E-143 E-138
STA. 388+93.17 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X																	VR-017		E-141
STA. 389+50.00 LT	EAST; VERMONT 2B; ←	1 1 1	30 36 21	15 36 15	3.13 9.00 2.19						2												2	X								X	M3-2 MI-5 M6-1		E-136B
	WEST; 2; ↑	1 1 1	30 36 21	15 36 15	3.13 9.00 2.19																												M3-4 MI-4 M6-3		E-136A
STA. 390+31.01 RT	EAST; 2	1 1	30 36	15 36	3.13 9.00						2			X		X																	M3-2 MI-4		E-136A
STA. 390+72.00 LT	0020 0303 0740	1	6	10	0.42						1	X			X																				E-138
STA. 392+75.00 LT	JCT; VERMONT 2B	1 1	21 36	15 36	2.19 9.00						2			X		X																	M2-1 MI-5		E-136B
STA. 393+31.01 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES; EMERGENCY STOPPING ONLY	1 1	36 30	36 24	9.00 5.00						2												2	X									VR-046 R8-7		E-142 E-142
STA. 396+31.01 RT	SPEED LIMIT 55	1	36	48	12.00						2			X		X																	R2-1		E-142
STA. 398+50.00 LT	1000 FEET	1 1	36 24	36 18	9.00 3.00						2			X		X																	W2-IMa (SMALL SIDE RIGHT) VP-136	59 59	
STA. 401+28.00 RT	0020 0303 0760	1	6	10	0.42						1	X			X																				E-138
STA. 401+50.00 LT	T.I.C.S.; T.I.C.S.; T.I.C.S.	1 1 1						24			2			X		X																	TO BE PAID FOR UNDER ITEM 680.20. "TRAVEL INFORMATION SIGNS" (NON-FEDERAL PARTIC.)		
STA. 411+84.00 LT	0020 0303 0780	1	6	10	0.42						1	X			X																				E-138
												FT 30	FT	FT 195*	FT 30	FT 195*	FT		EA	LB	LB	LB		LB 456.0	LB	LB	LB								
					SF 109.56	SF	EA. 2	SF 24				FT 225* *(INCL. 30' NON-FED. PARTIC.)			FT 225* *(INCL. 30' NON-FED. PARTIC.)					LB			EA. 4	LB 456.0				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 6

PROJECT NAME: DANVILLE - ST. JOHNSBURY
PROJECT NUMBER: NH 2501(1)S

FILE NAME: pave/05b034/05b034
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 05b034ts06.i

PLOT DATE: 16-FEB-2007
DRAWN BY: JAR
CHECKED BY: EPD