STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA. 422+10.66 LT	EMERGENCY STOPPING ONLY	1	30	24	5.00						1			X		X																	R8-7		E-142
STA. 422+17.66 RT	EMERGENCY STOPPING ONLY	1	30	24	5.00						1			X		X																	R8-7		E-142
STA. 422+24.91RT	BRIDGE 97 US 2	1	6	8	0.33						1	X			X																	VD-701		E-134
STA. 422+40.00 RT	0020 0303 0800	1	6	10	0.42						1	X			X																			E-138
STA. 422+56.37 LT	BRIDGE 97 US 2	1	6	8	0.33						1	X			X																	VD-701		E-134
STA. 432+26.85 RT	UNSAFE TO PASS	1	36	36	9.00						2			X		X																	VW-092		E-150
STA. 432+96.00 LT	0020 0303 0820	1	6	10	0.42						1	X			X																			E-138
STA. 434+11.61 LT	SLOWER TRAFFIC KEEP RIGHT	1	36	48	12.00						2			X		X																	R4-3		E-141
STA. 442+11.80 RT	BRIDGE 98 US 2	1	6	8	0.33						1	X			X																	VD-701		E-134
STA. 442+92.50 LT	BRIDGE 98 US 2	1	6	8	0.33						1	X			X																	VD-701		E-134
STA. 443+52.00 RT	0020 0303 0840	1	6	10	0.42						1	X			X																			E-138
STA. 446+37.57 RT	UNSAFE TO PASS	1	36	36	9.00						2			X		X																	VW-092		E-150
STA. 447+94.51 LT	EMERGENCY STOPPING ONLY	1	30	24	5.00						1			X		X																	R8-7		E-142
STA. 449+38.00 RT	EMERGENCY STOPPING ONLY	1	30	24	5.00						1			X		X																	R8-7		E-142
					SF 52.58	SF	EA.	SF				FT 70	FT	FT 150	FT 70	FT 150	FT		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					
												FT 220			FT 220					LB			EA.	LB											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 7

PROJECT NAME: DANVILLE - ST. JOHNSBURY
PROJECT NUMBER: NH 2501(1)S

FILE NAME: pave/05b034/05b034
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 05b034ts07.i

PLOT DATE: 12-JAN-2007
DRAWN BY: JAR
CHECKED BY: EPD
SHEET 54 OF 63