STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGNS	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 39+93.73 RT	THRU TRAFFIC KEEP RIGHT	1	36	48	12.00						2			X		X																	VR-118R		E-142
STA. 42+24.00 RT	0020 0311 0080	1	6	10	0.42						1	X			X																				E-138
STA. 46+03.09 RT		1	36	36	9.00						2			X		X																	W6-1		E-151
STA. 52+80.00 LT	0020 0311 0100	1	6	10	0.42						1	X			X																				E-138
STA. 61+77.60 LT	0020 0311 0117	1	6	10	0.42						1	X			X																				E-138
STA. 63+36.00 RT	0020 0311 0120	1	6	10	0.42						1	X			X																				E-138
STA. 64+45.55 LT	ONLY	1	48	30	10.00						2			X		X																	VR-935		E-145B
STA. 67+45.55 LT	NO. DANVILLE 4 → / VTRANS NORTHEAST CONSTRUCTION OFFICE → / WRONG WAY						3				2			X		X																			
STA. 70+45.55 LT	T.I.C.S. / T.I.C.S. / T.I.C.S.	1 / 1 / 1						24			2			X		X																	TO BE PAID FOR UNDER ITEM 680.20, "TRAVEL INFORMATION SIGNS" (NON-FEDERAL PARTIC.)		E-125
STA. 73+92.00 LT	0020 0311 0140	1	6	10	0.42						1	X			X																				E-138
STA. 132+68.67 RT	SPEED LIMIT 30	1	36	36	9.00						2			X		X																	W3-5	60	
STA. 132+91.52 LT	↑ DANVILLE 7 / ↑ MONTPELIER 37	1 / 1	72 / 72	12 / 12	6.00 / 6.00						2			X		X																	DI-1 / DI-1		E-123 / E-123
					SF 54.10	SF	EA. 3	SF 24				FT 50	FT	FT 210*	FT 50	FT 210*	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT 260* *(INCL. 30' NON-FED. PARTIC.)			FT 260* *(INCL. 30' NON-FED. PARTIC.)					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 9

PROJECT NAME: DANVILLE - ST. JOHNSBURY
PROJECT NUMBER: NH 2501(1)S

FILE NAME: pave/05b034/05b034
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: 05b034ts09.i

PLOT DATE: 16-FEB-2007
DRAWN BY: JAR
CHECKED BY: EPD
SHEET 56 OF 63