STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

			EROSION CONTROL	EMPLOYEE TRAINEE-SHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						1	1	m³	EARTH BORROW	203.30	EST.
						1	1	m³	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	EST.
						1880	1880	m²	COLD PLANING - BITUMINOUS PAVEMENT	210.10	35
						420	420	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST.
						4070	4070	T	AGGREGATE SHOULDERS	402.12	78
						346	346	T	AGGREGATE SHOULDERS (MOD.)	402.12	-
						31090	31090	KG	EMULSIFIED ASPHALT	404.65	610
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	EST.
						23100	23100	T	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30	255
					1		1	M	CONCRETE, CLASS A	501.22	EST.
					100		100	KG	REINFORCING STEEL	507.15	EST.
					23		23	M	BRIDGE RAILING H.D. STEEL BEAM CURB MTD. (MOD. 3)	525.40	0.2
						1	1	EA	CHANGING ELEVATION OF DI'S, CB'S OR MH'S	604.40	EST.
						1	1	EA	REHABILITATION OF DI'S, CB'S OR MH'S - CLASS I	604.412	EST.
						130	130	HR	POWER GRADER RENTAL	608.15	EST.
						140	140	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
						90	90	HR	POWER BROOM RENTAL	608.30	EST.
						130	130	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
						130	130	HR	TRUCK RENTAL	608.37	EST.
						130	130	HR	LOADER RENTAL, TYPE I	608.40	EST.
						359	359	m³	DUST CONTROL WITH WATER	609.10	8
						1	1	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	0.8
			870				870	m³	STONE FILL, TYPE I	613.10	EST.
						138	138	T	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	3.5
						365	365	M	STEEL BEAM GUARD RAIL	621.20	4
						215	215	M	STEEL BEAM GUARD RAIL W/2.4 METER POSTS (MOD.)	621.20	2.2
						40	40	M	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	0.5
						8	8	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
						2	2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
972	m²	TRANSITIONS
68	m²	BRIDGE NO. 17
648	m²	APPROACH CONSTRUCTION
157	m²	SIDEROADS
35	m²	ROUNDING
1880	m²	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		(PG 58-34)
8696	T	MAINLINE WEARING COURSE (TYPE IIIS)
8696	T	MAINLINE BINDER COURSE (TYPE IIIS)
235	T	TOWN HIGHWAYS (TYPE IIIS)
163	T	PARK-AND-RIDE (TYPE IIIS)
108	T	DRIVES (TYPE IIIS)
5	T	BRIDGE WEARING COURSE (TYPE IVS)
4941	T	LEVELING COURSE (TYPE IVS)
255	T	ROUNDING
23100	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

FINAL QUANTITIES ARE ARCHIVED WITH THE FIELD BOOKS

ARCHIVED IN DPR

PROJECT NAME : UNDERHILL--CAMBRIDGE

PROJECT NO.: STP 2212(11)S

DESIGN FILE NAME: /pave/99bl76/pbl76.dgn
IPARM FILE NAME: pbl76qsl.i
SURVEYED BY: D-H D-H
SQUAD LEADER: JLL
PLOT DATE: 26-JAN-2006
SURVEY DATE: 05/11/00
DRAWN BY: D-H
SHEET: 7 OF 36