STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
WESTFORD																																			
0+277.0, LT.	COWIE ROAD / STOP / 0150 0416 0018 / B-B						1																										INSTALL SALVAGED STREET SIGN 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET, MOUNTED ON NEW POST	-	-
		1	750	750	0.56						1			X																				E-143M
		1	150	200	0.03																														E-138M
0+296.1, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
3+609.2, LT.	ALLEN IRISH ROAD / ROUTE 15 / STOP						2				1			X																		INSTALL SALVAGED STREET SIGNS 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET, MOUNTED ON NEW POST	-	-
		1	750	750	0.56																														E-143M
3+619.2, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
	NO THRU TRUCKS						1																												-	-
3+621.1, RT.	LEGAL LOAD LIMIT 24,000 POUNDS						1				1			X																				-	-
	SPEED LIMIT 35						1																												-	-
3+631.8, RT.	BILL COOK ROAD / ROUTE 15 / STOP / 0150 0416 0225 / B-B						2				1			X																		INSTALL SALVAGED STREET SIGNS 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET, MOUNTED ON NEW POST. INSTALL NEW STOP SIGN AND SALVAGED REFERENCE PLAQUE BACK TO BACK ON NEW POST.	-	-
		1	750	750	0.56																													-	E-143M
							1																												-	-
CAMBRIDGE																																			
0+155.0, RT.	UNSAFE TO PASS						1				2			X																					-	-
							1																												-	-
1+771.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
1+788.0, RT.	CADY HILL ROAD / VT RTE 15 / STOP						2				1			X																		INSTALL SALVAGED STREET SIGNS 150 mm ABOVE NEW STOP SIGN USING POST TOP MOUNTING BRACKET, MOUNTED ON NEW POST	-	-
		1	750	750	0.56																														E-143M
														46.0																					
												m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m² 3.62		m²	EA. 13							m 46.0			m				kg			EA.	kg				EA.	EA.	kg					

ARCHIVED IN DPR

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

UNDERHILL - CAMBRIDGE
PROJECT NUMBER: STP 2212(I)S

FILE NAME: /pave/99bl76/pbl76.dgn
PROJECT LEADER: JLL
DESIGNED BY: D-H
IPARM FILE NAME: pbl76tsi.i

PLOT DATE: 26-JAN-2006 11:11
DRAWN BY: D-H
CHECKED BY:
SHEET 34 OF 36