STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 06

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
TOPSHAM (CONT.) 247+75, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
271+80, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
271+90, LT	BRIDGE 20 VT 25	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
272+24, RT	STOP 0250 0912 0513	1 1	30 6	30 10	6.25 0.42						1					X		X															SIGN ID CODE R1-1 SIGN ID CODE VD-700 MOUNTED BACK TO BACK AND BELOW STOP SIGN		E-143 E-138
272+33, LT	SPEED LIMIT 35	1	24	30	5.00						1					X		X															SIGN ID CODE R2-1		E-142
273+99, LT	BRIDGE 21 VT 25	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
275+41, LT	WEST TOPSHAM WAITS RIVER 3	1	30	18	3.75						1					X		X																	E-128B
279+73, LT	SCHOOL BUS STOP AHEAD	1	30	30	6.25						1					X		X															SIGN ID CODE S3-1		E-153
281+72, LT	SPEED LIMIT 35	1	36	36	9.00						2					X		X																70	
291+00, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
291+52, RT	KIMBALL HILL RD TH 25 STOP 0250 0912 0550	1 1	30 6	30 10	6.25 0.42		1				1					X		X															MOUNT MILE MARKER PLAQUE BACK TO BACK AND BELOW STOP SIGN.	- 	- E-143 E-138
299+83, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017		E-141
300+16, RT	STOP 0250 0912 0561	1 1	30 6	30 10	6.25 0.42						1					X		X															SIGN ID CODE R1-1 SIGN ID CODE VD-700 MOUNTED BACK TO BACK AND BELOW STOP SIGN		E-143 E-138
302+01, LT	STOP 0250 0912 0567	1 1	30 6	30 10	6.25 0.42						1					X		X															SIGN ID CODE R1-1 SIGN ID CODE VD-700 MOUNTED BACK TO BACK AND BELOW STOP SIGN		E-143 E-138
															FT 30	FT 195	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 71.34	SF	EA. 1	SF											FT 225				LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: BRADFORD-ORANGE
PROJECT NUMBER: STP 2213(1)

FILE NAME: p99b178.dgn PLOT DATE: 28-MAY-2010 13:4
PROJECT LEADER: JLL DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: JLL
IPARM_FILE: p99b178tss06.i SHEET 68 OF 84