STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

			NON-FED	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						460	460	m3	STONE FILL, TYPE I	613.10	8
						90	90	EA	YIELDING MARKER POSTS	619.17	EST.
						1175	1175	m	STEEL BEAM GUARDRAIL	621.20	11
						265	265	m	STEEL BEAM GUARDRAIL (2.4m POSTS) (MOD)	621.20	3
						143	143	m	HEAVY DUTY STEEL BEAM GUARDRAIL	621.21	0
						28	28	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	0
						11	11	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	0
						1750	1750	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	21
						5	5	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	0
						700	700	HR	UNIFORMED TRAFFIC OFFICERS	630.10	5
						1200	1200	HR	FLAGGERS	630.15	8
						1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17	-
						1	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
				520			520	HR	EMPLOYEE TRAINEESHIP	634.10	-
						1	1	LS	MOBILIZATION	635.10	-
						1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
						3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						22 285	22 285	m	DURABLE 100 mm WHITE LINE	646.40	227
						19 365	19 365	m	DURABLE 100 mm YELLOW LINE	646.41	190
						65	65	m	DURABLE 200 mm WHITE LINE	646.42	1
						145	145	m	DURABLE 600 mm STOP BAR	646.46	4
						56	56	EA	DURABLE LETTER OR SYMBOL	646.50	0
						44 560	44 560	m	TEMPORARY 100 mm WHITE LINE	646.60	444
						38 735	38 735	m	TEMPORARY 100 mm YELLOW LINE	646.61	385
						285	285	m	TEMPORARY 600 mm STOP BAR	646.66	3

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT : DOVER - STRATTON

PROJECT NO. : STP 2214(I)S

DESIGN FILE NAME: /pave/99b180/pb180.dgn
IPARM FILE NAME: pb180qs02.I
PLOT DATE: 24-MAY-2007
SURVEYED BY: CLD ENGINEERS INC
SURVEY DATE: 5/00
SQUAD LEADER: WRH
DRAWN BY: MPS
SHEET: 6 OF 49