STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

VAOT Metric

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.		NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		-	-	-	4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
		-	-	-	6700	6700	m	DURABLE 100 mm WHITE LINE	646.40	329
		-	-	-	5160	5160	m	DURABLE 100 mm YELLOW LINE	646.41	247
		-	-	-	60	60	m	DURABLE 150 mm WHITE LINE	646.414	4
		-	-	-	42	42	m	DURABLE 150 mm YELLOW LINE	646.415	2
		-	-	-	770	770	m	DURABLE 200 mm WHITE LINE	646.42	46
		-	-	-	30	30	m	DURABLE 600 mm STOP BAR	646.46	1.8
		-	-	-	67	67	EA	DURABLE LETTER OR SYMBOL	646.50	-
		-	-	-	45	45	m	TEMPORARY 100 mm WHITE LINE	646.60	3
		-	-	-	140	140	m	TEMPORARY 100 mm YELLOW LINE	646.61	13
		-	-	-	30	30	m	TEMPORARY 600 mm STOP BAR	646.66	1.8
		-	-	-	28	28	EA	TEMPORARY LETTER OR SYMBOL	646.70	-
		-	-	-	810	810	EA	LINE STRIPING TARGETS	646.76	40
		-	-	-	15	15	kg	SEED	651.15	EST.
		-	-	-	115	115	kg	FERTILIZER	651.18	EST.
		-	-	-	1	1	t	AGRICULTURAL LIMESTONE	651.20	EST.
		-	-	-	1	1	t	HAY MULCH	651.25	EST.
		-	-	-	25	25	m^3	TOPSOIL	651.35	EST.
		-	-	-	100	100	m^2	EROSION MATTING	654.10	EST.
		-	-	-	8	8	m^2	TRAFFIC SIGNS, TYPE A	675.20	0.91
								BEGIN OPTION ITEMS		
		-	-	-	75	75	m	FLANGED CHANNEL SIGN POSTS	675.301	6.0
			-	-	75	75	m	SQUARED TUBE SIGN POST AND ANCHORS	675.341	6.0
		-	-	-	18	18	EA	REMOVING SIGNS	675.50	-
		-	-	-	7	7	EA	ERECTING SALVAGED SIGNS	675.60	-
		-	-	-	7	7	EA	DELINEATORS W / STEEL POSTS	676.10	-
		-	-	-	2	2	EA	FLASHING BEACON - GROUND MOUNTED (MOD.)	678.16	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS				REMARKS
FROM	TO				+	-			
TOTALS									