ITEM DETAIL SUMMARY SHEET

VAOT Metric

LOCATION			GUARDRAIL										MISCELLANEOUS			REMARKS
			616.35	621.20	621.20	621.21	621.21	621.505	621.54	621.60	621.80	621.81	203.15	203.28	203.30	
STATION	STATION	POS.	TREATED TIMBER CURB	STEEL BEAM G.R.	STEEL BEAM G.R. W/2.4 m POSTS (MOD.)	HEAVY DUTY STEEL BEAM G.R.	H.D. STEEL BEAM G.R. W/2.4 m POSTS (MOD.)	MANUFACTURED TERMINAL SECTION	WOOD POST M.E.L.T.	ANCHOR FOR G.R.	REMOVE & DISP. G.R.	REMOVE & DISP. G.P.	COMMON EXCAVATION	EXCAVATION OF SURFACES AND PAVEMENT	EARTH BARROW	
			m	m	m	m	m	EA	EA	EA	m	EA	m^3	m^3	m^3	
ARLINGTON:																
11+575.0	11+833.6	LT	160	285.0				1			295.4					INSTALL TREATED TIMBER CURB FROM STA. 11+636.0 TO STA. 11+796.0. INSTALL NEW M.T.S. AT STA. 11+833.6.
11+678.7	11+800.3	RT		121.6				2			141					INSTALL NEW M.T.S. AT STA. 11+678.7 & STA. 11+800.3.
SUNDERLAND:																
0+162.2	0+458.6	LT	210	296.4				2			317					INSTALL TREATED TIMBER CURB FROM STA. 0+205.0 TO STA. 0+415.0. INSTALL NEW M.T.S. AT STA. 0+162.2 & STA. 0+458.6.
0+234.1	0+465.9	RT	125	231.8				2			252					INSTALL TREATED TIMBER CURB FROM STA. 0+291.0 TO STA. 0+416.0. INSTALL NEW M.T.S. AT STA. 0+234.1 & STA. 0+465.9.
0+645.0	0+707.0	LT											23.4	9	32.4	
SUBTOTAL			495	934.8				7			1005.4		23.4	9	32.4	
ROUNDING			25	55.2				-			54.6		1.6	1	2.6	
TOTAL			520	990				7			1060		25	10	35	

DATUM
VERTICAL N/A
HORIZONTAL N/A

ITEM DETAIL SUMMARY SHEET

SURVEYED BY N/A DATE N/A
DRAWN BY C.A.K. DATE 2/01
SQUAD LEADER T.P.K.
DESIGN FILE NO. /pave/99b198/pb198.dgn
IPARM FILE pb198id.I DATE PLOTTED 13-APR-2007 10:4
PROJ. NAME ARLINGTON - SUNDERLAND
PROJ. NO. STP 2223(I)S
SHEET 6 OF 16 SHEETS