STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ARLINGTON: 10+903.0, LT	DID NOT REPLACE	1	900	900	0.81						2			X																						E-150M
10+903.0, RT	3130 0201 0678 INSTALLED DID NOT REPLACE	1 1	900 150	900 200	0.81 0.03						2			X																				BACK - TO - BACK		E-150M E-138M
11+566.5, LT	STOP 3130 0201 0719 DID NOT REPLACE INSTALLED	1 1	750 150	750 200	0.56 0.03						1			X																				BACK - TO - BACK		E-143M E-138M
11+576.5, RT	STOP 3130 0201 0719 DID NOT REPLACE INSTALLED	1 1	750 150	750 200	0.56 0.03						1			X																				BACK - TO - BACK		E-143M E-138M
11+582.5, LT	900X900X900	1			0.70						1			X																						E-146M
11+604.2, LT	DID N OT INSTALL ABANDONED	1	750	750	0.56						1			X																						E-140M
		m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg																				
				36.8																																
TOTALS		m^2 4.09	m^2	EA	m^2		m 36.8		m		kg	EA	kg			EA	EA	kg																		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: ARLINGTON - SUNDERLAND
PROJECT NO.: STP 2223(I)S

DESIGN FILE NAME: /pave/99b198/pb198.dgn
IPARM FILE NAME: pb198ssi.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 17-APR-2007 10
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 14 OF 16