NYSDOT ESTIMATE OF QUANTITIES

ITEM NUMBER	DESCRIPTION	UNIT	QUANTITY	
01619.2101 M	SOLAR PORTABLE VARIABLE MESSAGE DISPLAY UNIT	EA	5	
620.02 M	STONE FILLING (FINE)	m^3	15	
620.03 M	STONE FILLING (LIGHT)	m^3	14	
620.04 M	STONE FILLING (MEDIUM)	m^3	25	
625.04 M	CONCRETE R.O.W MARKERS TYPE L (LOW)	EA	16	
625.05 M	STEEL PIN AND CAP RIGHT-OF-WAY MARKERS	EA	7	
645.7102 M	GROUND MOUNTED SIGN PANEL, MUTCD CODES R,P,W AND M, 461 TO 762 mm	m^2	22	
645.7103 M	GROUND MOUNTED SIGN PANEL, MUTCD CODES R,P,W AND M, 763 TO 1625 mm	m^2	11	
645.73 M	GROUND MOUNTED SIGN PANELS, MUTCD CODES G & I	m^2	18	
645.81 M	TYPE A SIGN POST	EA	52	
645.8106 M	HIGH CAPACITY TYPE A SIGN POST	EA	4	
645.830402 M	TYPE B SIGN POST, GALVANIZED, W200X22.5 SECTION, BI-DIRECTIONAL BREAKAWAY BASE	EA	2	
646.0601 M	DELINEATOR, SINGLE UNIT, ONE WAY, ON POST	EA	100	
646.0602 M	DELINEATOR, SINGLE UNIT, BACK TO BACK, ON POST	EA	23	
646.0603 M	DELINEATOR, SINGLE UNIT, TWO WAY, ON POST	EA	5	
646.0604 M	DELINEATOR, SINGLE UNIT, THREE WAY, ON POST	EA	2	
646.0701 M	REFERENCE MARKER, 1.2 m MOUNTING HEIGHT	EA	13	
646.0705 M	REFERENCE MARKER, FURNISH PANEL ONLY	EA	3	
646.0801 M	SNOW PLOWING MARKER, SINGLE UNIT	EA	6	
646.0802 M	SNOW PLOWING MARKER, DOUBLE UNIT	EA	7	
646.0803 M	SUPPLEMENTARY SNOW PLOWING MARKER	EA	8	
647.01 M	REMOVAL OF SIGNS - SIZE A (0.0 TO 1.0 sm)	EA	1	
647.02 M	REMOVAL OF SIGNS - SIZE B (1.1 TO 2.0 sm)	EA	1	
655.0201 M	FRAMES & GRATES (FABRICATED)	EA	3	
655.0501 M	STEEL FABRICATED GRATES IN CAST IRON FRAMES	EA	1	
680.5001 M	POLE EXCAVATION AND CONCRETE FOUNDATION	m^3	6	
680.510501 M	PULLBOX-RECTANGULAR 650 mm x 450 mm, REINFORCED CONCRETE	EA	2	
680.520103 M	CONDUIT METAL STEEL, ZINC COATED, 1 NPS	m	10	
680.520106 M	CONDUIT METAL STEEL, ZINC COATED, 2 NPS	m	5	
680.603011 M	TRAFFIC SIGNAL POLE-SPAN WIRE, 30 kN LOAD, 11 m	EA	2	
680.7002 M	DUAL SPAN WIRE WITH UPPER TETHER WIRE	EA	1	
680.730514 M	SIGNAL CABLE, 5 CONDUCTOR, 14 AWG	m	140	
680.731514 M	SIGNAL CABLE, 15 CONDUCTOR, 14 AWG	m	40	
15680.806202 M	INTERSECTION FLASHER (SOLID STATE) WITH CABINET	EA	1	
680.810101 M	TRAFFIC SIGNAL MODULE - 300 mm, RED BALL, LED	EA	2	
680.810103 M	TRAFFIC SIGNAL MODULE - 300 mm, YELLOW BALL, LED	EA	4	
680.810107 M	TRAFFIC SIGNAL SECTION, TYPE 1, 300 mm	EA	6	
680.8204 M	OVERHEAD SIGN ASSEMBLY, TYPE D	EA	1	
01680.9092 M	ELECTRIC METER SOCKET, 100A, SINGLE PHASE, 120V	EA	1	
15680.94 M	RAINTIGHT DISCONNECT BOX	EA	1	
15680.950106 M	POWER CABLE, 1 CONDUCTOR, 6 AWG	m	100	
685.11 M	WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES - 0.51 mm	m	5520	
685.12 M	YELLOW EPOXY REFLECTORIZED PAVEMENT STRIPES - 0.51 mm	m	10700	
688.01 M	WHITE PREFORMED REFLECTORIZED PAVEMENT STRIPES	m	60	
688.03 M	WHITE PREFORMED REFLECTORIZED PAVEMENT LETTERS	EA	8	
688.04 M	WHITE PERFORMED REFLECTORIZED PAVEMENT SYMBOLS	EA	2	
691.1001 M	TRAINING REQUIREMENTS	HR	520	
699.04 M	MOBILIZATION (4%)	LS	NEC	

Metric

FED. ROAD REG. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.	TOTAL SHEETS
1	N.Y.	0146001	14	92

BENNINGTON CONNECTOR S.H. 98-2
P.I.N. 1306.60
WHITEHOUSE BRIDGE - VERMONT STATE LINE S.H. 1426
RENSSELAER COUNTY

IN CHARGE OF T. KARIS DESIGNED BY D. EMERICH CHECKED BY D. GOZALKOWSKI ESTIMATED BY D. EMERICH CHECKED BY D. GOZALKOWSKI DRAFTED BY C. KAHLBAUGH CHECKED BY T. BURTNICK DATE 2/04

FILE NAME = u:\51i6\nysdot\contract1\nyquan.dgn
DATE/TIME = 2/23/2004
USER = 2225

NYSDOT ESTIMATE OF QUANTITIES

SURVEYED BY C.H.A. & V.S.E. DATE 12/93
DESIGNED BY D.W.E. DATE 2/04
DRAWN BY C.A.K. DATE 2/04
CHECKED BY T.P.K. DATE 2/04

DESIGN FILE NO. NYQUAN.DGN

PROJ. NAME BENNINGTON - HOOSICK D.P.I. 0146(1) C/1

PROJ. NO. P.I.N. 1306.60

SHEET 14 OF 92 DWG NO. NYQ-2