FED. ROAD REG. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.	TOTAL SHEETS
1	N.Y.	0146001	61	92

BENNINGTON CONNECTOR S.H. 98-2

P.I.N. 1306.60

WHITEHOUSE BRIDGE - VERMONT STATE LINE S.H. 1426

RENSSELAER COUNTY

SIGNS TO BE INSTALLED

ITEM NO. SIGN PANEL	ITEM NO. SIGN SUPPORT	SIGN SUPPORT, NUMBER REG'D PER SIGN	STATION LOCATION	TEXT	N.Y.S. M.U.T.C.D. NO.	APPROX. SIZE OF SIGN
645.7102 M	645.81 M	2	42+980.0, RT	* TO VERMONT 279 ↑ · EAST 7 → · * TO VERMONT 9 →	MI3-2IX MI3-I3X MI3-2IX M3-2X(MOD) M3-IX M3-IX(MOD) MI3-43X MI3-32X MI3-32X	600X300 600X300 600X300 750X600 600X600 600X600 525X375 525X375 525X375 (2.30 m²)
645.7103 M	645.81 M	2	43+092.0, RT 43+300.0, RT 43+740.0, RT	SLOWER TRAFFIC KEEP RIGHT	R4-I5D	900X1200 (1.08 m²)
645.7102 M	645.81 M	2	43+210.0, RT	* TO VERMONT 279 ↑ · EAST 7 → · * TO VERMONT 9 →	MI3-2IX MI3-I3X MI3-2IX M3-2X(MOD) M3-IX M3-IX(MOD) MI3-43X MI3-42X MI3-42X	600X300 600X300 600X300 750X600 600X600 600X600 525X375 525X375 525X375 (2.30 m²)
645.7103 M	645.81 M	2	43+140.0, LT 43+360.0, RT 45+060.0, LT	STATE SPEED LIMIT 55	R2-2D	900X1200 (1.08 m²)
645.7102 M	645.81 M	1	43+180.0, LT	WEST 7	MI3-I4X M3-IX	600X300 600X600 (0.54 m²)
645.7103 M	645.81 M	2	43+245.0, LT	⟷	W2-I8D	1200X600 (0.72 m²)
645.7102 M	645.81 M	2	43+280.0, LT	* EAST 7 ← KEEP RIGHT · TO VERMONT 9 ← KEEP RIGHT · WEST 7 ↑	MI3-I3X MI3-2IX MI3-I4X M3-IX M3-IX(MOD) M3-IX MI3-4IX MI3-4IX MI3-43X	600X300 600X300 600X300 600X600 600X600 600X600 525X375 525X375 525X375 (2.21 m²)
645.7102 M	645.81 M	1	43+335.0, RT	* TO VERMONT 279 ↑	MI3-2IX M3-2X(MOD) MI3-43X	600X300 750X600 525X375 (0.83 m²)
645.7102 M	645.81 M	2	143+305.0, RT	EAST 7 · * TO VERMONT 9 ↑	MI3-I3X MI3-2IX M3-IX M3-IX(MOD) MI3-43X	600X300 600X300 600X600 600X600 525X375 (1.28 m²)
645.7102 M	645.81 M	2	143+285.0, LT	WEST 7 ← · * TO VERMONT 279 →	MI3-I4X MI3-2IX M3-IX M3-2X(MOD) MI3-4IX MI3-42X	600X300 600X300 600X600 750X600 525X375 525X375 (1.56 m²)
645.7102 M	645.81 M	1	143+365.0, RT	STATE SPEED LIMIT 55	R2-2C	600X750 (0.45 m²)

* PAYMENT FOR ALL VERMONT ROUTES 279 AND 9 SIGNS WILL BE MADE UNDER N.Y.S. M.U.T.C.D. NO. AND SIZE SHOWN. HOWEVER, SIGN MATERIALS, COLORS, LETTERING AND SPECIFICATIONS SHALL MEET THE REQUIREMENTS OF VERMONT STANDARD SHEET E-136BM INCLUDED IN THE SPECIAL PROVISIONS.

SIGNS TO BE INSTALLED

ITEM NO. SIGN PANEL	ITEM NO. SIGN SUPPORT	SIGN SUPPORT, NUMBER REG'D PER SIGN	STATION LOCATION	TEXT	N.Y.S. M.U.T.C.D. NO.	APPROX. SIZE OF SIGN
645.7102 M	645.81 M	1	143+440.0, LT	WEST 7 ← · * TO VERMONT 279 →	MI3-I4X MI3-2IX M3-IX M3-2X(MOD) MI3-3IX MI3-32X	600X300 600X300 600X600 750X600 525X375 525X375 (1.56 m²)
645.7102 M	645.81 M	2	43+140.0, RT	BENN HIST DISTS HISTORIC SITE → · BENN BATTLE MONUMENT HISTORIC SITE → · H → · ? →	M9-2C M9-2C MI4-42X MI4-42X MII-IC MI0-7C MI4-42X MI4-42X	750X600 750X600 525X375 525X375 600X600 600X600 525X375 525X375 (2.41 m²)
645.7102 M	645.81 M	2	43+500.0, LT	* TO VERMONT 9 ↰ · 7 ↵	MI3-I3X M3-IX(MOD) M3-IX MI3-3IX MI3-54X	600X300 600X600 600X600 525X375 525X375 (1.29 m²)
645.7103 M	645.81 M	2	44+700.0, LT 45+020.0, LT	DO NOT PASS	R4-ID	900X1200 (1.08 m²)
645.73 M	645.830402 M	2	45+100.0, LT	WELCOME TO NEW YORK The Empire State	II2-4D	3450X2250 (7.76 m²)
645.7102 M	645.81 M	1	43+560.0, LT	JCT 7	MI3-IX M3-IX	600X300 600X600 (0.54 m²)
645.7103 M	645.81 M	2	143+500.0, LT	STOP AHEAD	W2-I5C	900X900 (0.81 m²)
645.7102 M	645.81 M	1	43+230.0, RT 43+260.0, RT	STOP	RI-I	750X750 (0.56 m²)

NOTE:
ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE NOTED.

SIGN TEXT DATA

SURVEYED BY C.H.A. & V.S.E. DATE 12/93
DESIGNED BY D.W.E. DATE 2/04
DRAWN BY C.A.K. DATE 2/04
CHECKED BY T.P.K. DATE 2/04

DESIGN FILE NO. NYSTDI.DGN

PROJ. NAME BENNINGTON - HOOSICK D.P.I. 0146(1) C/1

PROJ. NO. P.I.N. 1306.60

SHEET 61 OF 92 DWG NO. STD-1

DESIGNED BY D. EMERICH CHECKED BY D. GOZALKOWSKI DRAFTED BY C. KAHLBAUGH CHECKED BY I. BURTNICK DATE 2/04
ESTIMATED BY D. EMERICH CHECKED BY D. GOZALKOWSKI
IN CHARGE OF T. KARIS

FILE NAME = \pt5116\nysdot\contracts1\nystdi.dgn
DATE/TIME = 2/23/2004
USER = 2225